



## Department of Energy

Idaho Operations Office  
785 DOE Place  
Idaho Falls, Idaho 83402

December 3, 1990

Mr. Michael Gearheard, Chief  
Waste Management Branch  
U. S. Environmental Protection Agency  
Region 10  
1200 Sixth Avenue  
Seattle, WA 98101

SUBJECT: Final Closure Report for CPP-55, Mercury Contaminated Area

Dear Mr. Gearheard:

This correspondence forwards the Final Closure Report for COCA unit CPP-55, Mercury Contaminated Area, to your office for review and approval. The Closure Plan for this site was submitted on January 27, 1989. The plan was jointly approved by the state of Idaho and EPA Region 10 on September 19, 1989. The letter of approval indicated that, "INEL may proceed with implementation of closure activities per the Closure Plan submitted 1/27/89." These closure activities included site characterization necessary to determine the amount of contaminated material to be removed.

This report evaluates the results of closure activities completed at the site, identifies the absence of RCRA hazardous constituents, and recommends that the unit be clean closed under RCRA with no waste removal necessary. The report concludes that this unit poses no risk to human health or the environment. Therefore, no further action at this site is recommended.

If you have any questions, please contact W. N. Sato at (208) 526-0193 or L. A. Green at (208) 526-0417.

Sincerely,

A handwritten signature in cursive script, reading "J. E. Solecki".

J. E. Solecki, Acting Assistant Manager  
Environmental Restoration and  
Waste Management

Enclosure

cc: C. R. Koshuta, IDHW, w/encl. (2)  
L. J. Mann, USGS, w/encl.  
I. Resendez, DOE-ID, w/o encl.  
C. R. Enos, DOE-ID, w/encl.  
O. K. Earle, WINCO, w/o encl.  
D. J. Blumberg, EG&G, w/o encl.  
J. Rodin, EPA, w/o encl.  
ERP ARDC, w/encl.

218471

November 21, 1990

**FINAL REPORT FOR  
CLOSURE OF CPP-55,  
MERCURY CONTAMINATED AREA  
(SOUTH OF ICPP T-15)**

## CONTENTS

### FINAL REPORT FOR CLOSURE OF CPP-55, MERCURY CONTAMINATED AREA (South of ICPP T-15)

1. FACILITY CONDITIONS . . . . .	1
1.1 General Description . . . . .	1
1.2 Unit Characterization Objectives . . . . .	5
1.3 Closure Goals . . . . .	6
2. GEOLOGY . . . . .	6
2.1 General Geology . . . . .	6
2.2 Site Specific Geology . . . . .	7
3. HYDROGEOLOGICAL CHARACTERIZATION . . . . .	8
3.1 Surface Water . . . . .	8
3.2 Groundwater . . . . .	9
4. WASTE TYPES KNOWN OR SUSPECTED . . . . .	9
5. PRE-CLOSURE SAMPLING AND ANALYTICAL RESULTS . . . . .	10
5.1 Unit Sampling . . . . .	12
5.1.1 Sampling Locations . . . . .	12
5.1.2 Drilling . . . . .	12
5.1.3 Sampling Methods. . . . .	15
5.2 Background Sampling . . . . .	16
5.3 Quality Assurance Samples . . . . .	18
5.4 Radiation Survey . . . . .	20
5.5 Sample Preservation Methods and Holding Times . . . . .	20
5.6 Sample Packing and Shipping . . . . .	21
5.7 Data Validation, Evaluation, and Reporting . . . . .	21
5.7.1 Data Validation . . . . .	21
5.7.2 Data Evaluation . . . . .	23
5.7.3 Data Reporting . . . . .	25
5.8 Sample Analysis . . . . .	25
5.8.1 Chemical/Radiological Sample Analysis . . . . .	25
5.8.2 Quality Assurance Sample Analysis . . . . .	32
6. CLOSURE PROCEDURES . . . . .	33
7. DECONTAMINATION PROCEDURES . . . . .	33
8. POST-REMOVAL SAMPLING AND ANALYTICAL PROCEDURES . . . . .	34
9. CLOSURE QUALITY ASSURANCE/ QUALITY CONTROL PROCEDURES . . . . .	34
10. CLOSURE CERTIFICATION . . . . .	35
11. AREA RESTORATION . . . . .	35

12. OTHER TOPICS OF CONCERN . . . . .	35
13. SCHEDULE OF ACTIVITIES . . . . .	35
14. POST CLOSURE . . . . .	35
15. REFERENCES . . . . .	37

## APPENDICES

APPENDIX A HEALTH AND ENVIRONMENTAL ASSESSMENT

APPENDIX B BOREHOLE LOGS

APPENDIX C QUALITY ASSURANCE SAMPLE ANALYSIS RESULTS

APPENDIX D BOREHOLE CPP-55-06 ANALYSES

## LIST OF FIGURES

Figure 1. Idaho Chemical Processing Plant . . . . .	2
Figure 2. LDU CPP-55 Location map . . . . .	3
Figure 3. LDU CPP-55 Photo location map . . . . .	4
Figure 4. Sampling locations and borehole numbers . . . . .	13
Figure 5. Background sampling locations . . . . .	17

## LIST OF TABLES

Table 1. Target Compound/Analyte List . . . . .	11
Table 2. Background Sample Analysis Results . . . . .	19
Table 3. Inorganic Sample Analysis Results . . . . .	27
Table 4. EP-Toxicity Analysis Results . . . . .	29
Table 5. Organic Sample Analysis Results . . . . .	30
Table 6. Inorganic and Radiologic Analysis Results from Borehole CPP-55-06 . . . . .	31
Table A.1 Summary of HEA for LDU CPP-55. . . . .	A-4
Table C.1 Organic Trip Blank Analysis Results. . . . .	C-1
Table C.2 Equipment Blank Analysis Results . . . . .	C-2
Table C.3 Field Blank Analysis Results . . . . .	C-3
Table C.4 Field Duplicate Analysis Results, (mg/Kg). . . . .	C-4
Table C.5 Blind Sample Analysis Results. . . . .	C-6
Table C.6 Decontamination Rinseate Analysis Results. . . . .	C-7
Table D.1 List of Analytes/Compounds Analyzed for in Samples from Borehole CPP-55-06. . . . .	D-1
Table D.2 List of Analytes/Compounds Analyzed for But Not Detected, from Borehole CPP-55-06 Samples. . . . .	D-4

## EXECUTIVE SUMMARY

Land Disposal Unit (LDU) CPP-55 was characterized during the winter of 1989-1990, in accordance with the requirements of the INEL Consent Order and Compliance Agreement (COCA) and as outlined in the closure plan approved September 1989, to determine the nature and extent of any contamination at the unit. The results of this characterization work were then reviewed by the sampling subcontractor (Golder Associates, Inc.) and WINCO Environmental Restoration and used to determine the specific requirements for unit closure under RCRA (40 CFR 265, Subpart G).

LDU CPP-55 is located inside the Idaho Chemical Processing Plant (ICPP) security fence adjacent to the south side of building T-15 and covers an area of approximately 4,000 ft<sup>2</sup>. During an environmental study of controlled pollutants at the ICPP in 1984, non-plant subcontractors were observed discarding paint solvents, used during cleanup operations, to the soil adjacent to building CPP T-15. It is believed that paint solvents were also discarded to the soil in this area on other occasions. WINCO assumes that the disposal practice began soon after the building was occupied in 1982, and that the practice occurred sporadically until 1984.

Drilling to six feet at ten locations was conducted between December 19, 1989 and January 5, 1990. The drilling operations for the deep borehole to a depth of 123 feet, were conducted from February 6 to February 22, 1990. Five inorganic hazardous constituents (arsenic, chromium, lead, silver, and mercury) were detected above background levels. Mercury was the only constituent detected in more than two samples, but nowhere exceeded the EP-Toxicity limit of 0.2 mg/L. Organic analysis identified three common laboratory contaminants (toluene, 4-methyl 2-pentanone, and bis (2-ethylhexyl) phthalate) each in two separate samples. These were removed from further consideration by validation procedures. Again, none of these were above regulatory or health based levels.

The five inorganic constituents detected were each subjected to a Health and Environmental Assessment, as recommended in the RCRA Facility Investigation Guidance. The results of this assessment (see Appendix A) indicate that the hazardous constituents present at LDU CPP-55 do not pose an unacceptable risk to human health, safety, or the environment. Results showed that the highest non-cancer risk factor to be from ingestion of chromium contaminated soil (at  $1.3 \times 10^{-5}$  for a residential adult scenario). Risk associated with the most wide spread contaminant found, mercury, is at the  $1.0 \times 10^{-6}$  level for the same scenario. The cancer risk factor for all exposure scenarios was found to be in the  $1 \times 10^{-6}$  level.

In conclusion, all RCRA hazardous constituents detected at LDU CPP-55 were present below regulatory limits and can be shown not to pose any potential threat to human health, safety, or the environment. For these reasons there does not appear to be any basis for remediation or post-closure activities at this site. RCRA requirements under 40 CFR 265, Subpart G address only those sites with hazardous waste present. Since no RCRA wastes are present above regulatory limits, it is being recommended that LDU CPP-55 be clean closed

without removal actions. If any future activity is deemed necessary, under the upcoming INEL Interagency Agreement, it will be completed at that time under that agreement.

FINAL REPORT FOR  
CLOSURE OF CPP-55,  
MERCURY CONTAMINATED AREA  
(South of ICPP T-15)

EPA Facility ID No.: ID 4890008952

Owner/Operator: Dept. of Energy, Idaho Operations Office  
Address: 785 DOE Place  
Idaho Falls, Idaho 83402  
(208) 526-1505

Facility Address: Idaho Chemical Processing Plant  
Scoville, Idaho

1. FACILITY CONDITIONS

1.1 General Description

The mercury contaminated area designated as Land Disposal Unit (LDU) CPP-55 is located inside the Idaho Chemical Processing Plant (ICPP) security fence south of temporary building ICPP T-15 (N 695,087; E,297,607) (see Figures 1, 2 and 3). As stated in the approved closure plan (WINCO, 1989), the area designated as LDU CPP-55 was located as a result of an environmental study of controlled pollutants at the ICPP in 1984. At that time, a non-plant subcontractor was observed discarding paint solvents to the soil adjacent to building CPP T-15. WINCO assumes that the disposal practice began soon after the building was occupied in 1982, and that the practice occurred sporadically until being discovered and prohibited in 1984. LDU CPP-55 is adjacent to the south side of building T-15, where doors are present, and covers an area of approximately 4,000 ft<sup>2</sup> (see Figure 2).

Since there are no records of the incidents, beyond the single citing, and the materials did not visibly stain the soil, the area established








Figure 2. CPP-55 Location Map




Figure 3. Photo location of CPP-55.

for the unit covers most of the ground between T-15 and the surrounding roadway (see Figure 2). The exact volume of paint solvents discarded to the soil is unknown, but WINCO believes the volume is small ( $< 1$  gal/occurrence). This belief is based on the activity observed and the knowledge that cleaning paint brushes utilizes small quantities of solvents. The area is currently being used for storage of construction materials.

Seven soil samples analyzed during an unrelated study in August 1985, for mercury and cadmium showed mercury levels ranging from 48 to 236 parts per billion (ppb). The EP-Toxicity limit for mercury is 200 ppb. On the basis of one sample, at 236 ppb, exceeding the EPA limit this unit was classified as an LDU. It should be noted that non-EPA methods were used that were more rigorous and therefore led to more conservative values. As is discussed below, this is borne out by these most recent analysis results. Since heavy metals are a constituent of some paint pigments, it is believed that the relatively high concentrations of mercury at the unit were a result of the former waste paint and solvent discarding practice. There are no processing or storage facilities, other than T-15, in the immediate vicinity of the unit from which contamination could have been contributed.

## 1.2 Unit Characterization Objectives

Land Disposal Unit CPP-55 was characterized in accordance with the Idaho National Engineering Laboratory (INEL) Consent Order and Compliance Agreement (COCA) and the approved closure plan. Objectives were to determine if any RCRA hazardous wastes or constituents associated with the disposal practice were present in the soil and, if so, to determine the nature and extent of any such contamination. This information will be utilized to evaluate the closure options for the unit as discussed below.

### 1.3 Closure Goals

DOE's closure goals, based on the characterization results described herein, are to:

- Eliminate this unit from further consideration under the COCA, since no RCRA hazardous waste or constituents were detected above regulatory limits, and those detected do not pose a risk to human health or the environment.
- Consider the unit clean closed without removal.
- Meet the commitments of the closure plan submitted in January 1989 and approved in September 1989.

## 2. GEOLOGY

The following is presented as additional information to that supplied in the approved closure plan of September 1989. This material is related more specifically to the ICPP than that presented earlier.

### 2.1 General Geology

Surficial sediments at the ICPP, and much of the INEL, consists of deposits of well graded gravels, sands, and intermittent silt, and sandy clay lenses. Surface alluvium extends to the top of the basalt, generally around 35 to 50 feet. In many areas around the ICPP there exist a layer of fine grained sandy clay and clayey or silty sand at the basalt/surface sediment interface. This layer ranges from 0 to 10 feet thick. Hydraulic conductivity of this fine grained material ranges from  $1 \times 10^{-6}$  to  $3 \times 10^{-2}$  cm/sec. Hydraulic conductivity of the coarser surface material ranges from  $3 \times 10^{-3}$  to  $2 \times 10^{-1}$  cm/sec (Cooper, 1988).

The subsurface stratigraphy of the Eastern Snake River Plain (ESRP) consists of thin (averaging <25 feet) basaltic lava flows with numerous interbedded sediments and cinder zones. The sediments are of lacustrine, eolian, and fluvial origins with source areas in the

neighboring mountain ranges. These sediments also occur as fracture fillings in the basalt flows. Composition of the flows are mainly a very dark gray to black, variably vesicular, olivine basalt. Exact composition of the interbeds in the area of the ICPP is yet to be determined. However, they can reasonable be expected to be similar to the current surface sediments. This sequence of flows and interbeds extends for a depth of 2000 to 3000 feet (Doherty, et.al., 1979).

Underlying these basalt flows is a thick (5000 feet) sequence of welded rhyolite tuffs. Interbedded within these welded tuffs are layers of tuffaceous sands, air-fall ash, and ash flow tuffs (Doherty, et.al., 1979).

The deepest rocks encountered at the INEL are a dense, hydrothermally altered, recrystallized, aphanitic, rhyodacite porphyry. This unit extends from approximately 8100 feet to below 10,300 feet (Doherty, et.al., 1979).

## 2.2 Site Specific Geology

Surface soils at LDU CPP-55 were disturbed prior to disposal activities to variable depths estimated at 4 to 8 feet below ground. Shallow soil samples taken within this zone consisted of unstratified, dense to very dense, coarse sand and fine to coarse gravel with (<12%) silt. Gravels are well rounded, while the sand grains are sub-angular to sub-rounded. Below this zone of disturbed soils dense to very dense material, of similar composition, extends to 40.3 feet. Generally, resistance to drilling increased when natural alluvium was encountered. The interval from 40.3 feet to the top of the basalt (43.7 feet) consisted of a firm to soft, damp to moist, silt to clayey silt layer with trace sand (<5%). Total thickness of surface sediments at the unit is approximately 43.7 feet.

The basalt under LDU CPP-55, to a total depth of the borehole at approximately 123 feet, is a fresh, medium dark gray to dark gray,

vesicular, aphanitic rock of medium strength. Scattered fractures and localized fracture zones were encountered. Interbeds, above 119 feet, consisted of unstratified, fine sand with little silt and clay. The interbed below 119 feet consisted of a stiff to hard, damp, non-stratified, clayey silt to silty clay. Stratigraphy below 123 feet is assumed to be similar to that described in Section 2.1 above.

### 3. HYDROGEOLOGICAL CHARACTERIZATION

The following information is provided as additional clarifying information to that presented in the September 1989 approved closure plan. This current information is more applicable to the ICPP area. The information supplied in the approved closure plan was based on regional hydrogeologic information.

#### 3.1 Surface Water

The only surface water feature in the area of the ICPP is the dry channel of the Big Lost River. Water flow in the river is intermittent, with flows reaching to the ICPP area only during years of high spring run-off and snow melt from the surrounding mountains. The last time water reached the ICPP area was in 1987, when the river flowed for the entire year. Even during these wet years the river will normally only flow in the winter and spring months. The main channel of the Big Lost passes within approximately 20 feet of the northwest corner of the ICPP. The general slope of the surface for the ICPP is towards the river at approximately 0.07%.

### 3.2 Groundwater

All subsurface water at the ICPP, including the Snake River Plain Aquifer (SRPA), is under water table conditions. Due to the low permeability of the sedimentary interbeds various perched zones are formed as surface infiltration percolates down through the basalt. There are four perched zones of concern, with the zone at the 110 foot level designated, as per the RCRA definition, as the uppermost aquifer. It is agreed, however, that the deeper SRPA is the main aquifer of concern. These zones occur at:

- the sediment/basalt interface (approximately 40 - 50 feet below ground)
- the 110-foot interbed (a zone of thin basalt flows and sediment interbeds ranging from 90 to 120 feet below ground, and averaging approximately 50 - 60 feet thick)
- the 265-foot interbed (a low permeability cinder zone approximately 30 feet thick)
- the 365-foot interbed (another low permeability clay interbed approximately 20 feet thick)

These perched zones can be permanently formed under areas of constant infiltration (e.g., as beneath the percolation pond and sewage treatment trenches). However, the interbed permeability is such that, should the constant source be removed, these zones will dissipate in seven to eight months. Indications are that there is no hydraulic connection between these interbeds. The areal extent of these perched zones is under investigation.

### 4. WASTE TYPES KNOWN OR SUSPECTED

The waste type most likely to occur would be a mixture of paint diluted in paint thinner, which resulted from cleaning painting equipment (e.g., brushes and rollers). The quantity of wastes discarded at the unit is unknown, and the actual disposal locations could not be determined because the soil was not visibly stained by the solvents and there are no records of the incidents.

There are no records of the actual types or quantities of materials discarded at the unit. However, listed below are some of the more "typical" organics and heavy metals used in paints and paint thinners at the time of disposal (DeVoe Paints, 1990).

<u>Solvents</u>	<u>Heavy Metals</u>
Acetone	Cadmium
Benzene	Chromium
2-Butanone	Iron
Mineral spirits	Lead
Toluene	Mercury
Xylene	Nickel

The soil analyses conducted at the time of the incident (see Section 1.1) showed mercury contamination in the soil column to a depth of six inches, but these analyses can not be considered adequate for unit characterization because they were not conducted for organic solvents or heavy metals, other than mercury, and cadmium; also the analyses were not conducted before EPA approved methods were available. For these reasons, further characterization of the unit was deemed necessary to determine the nature and extent of contaminated soil.

#### 5. PRE-CLOSURE SAMPLING AND ANALYTICAL RESULTS

As discussed in the approved closure plan, a two phased sampling plan was conducted for unit characterization. The first phase consisted of shallow soil sampling (6 feet) to determine if any hazardous constituents listed in Table 1 were present above the regulatory thresholds. Selected samples were analyzed for full 40 CFR 261 Appendix VIII and Target Compound List constituents (Appendix D.1). The second phase consisted of a deep borehole, to the upper confining layer, at 110 feet, to determine if any contamination had migrated to the perched groundwater below the unit.

Sampling and analysis activities were conducted by an independent sampling contractor (Golder Associates, Inc. of Redmond, WA), whose QA/QC program was reviewed and approved by WINCO QA auditors, prior to initiating work. The



Table 1.

Compound/Analyte	Compound/Analyte
<u>Organics</u>	<u>Metals</u>
Chloromethane	Arsenic
Bromomethane	Barium
Vinyl Chloride	Cadmium
Methylene Chloride	Chromium
Acetone	Iron
Carbon Disulfide	Lead
1,1-Dichloroethane	Mercury
1,1-Dichloroethene	Nickel
1,2-Dichloroethene (total)	Selenium
Chloroform	Silver
1,2-Dichloroethane	
2-Butanone	<u>Radionuclides</u>
1,1,1-Trichloroethane	Americium 241
Carbon Tetrachloride	Plutonium 238
Vinyl Acetate	Neptunium
Bromodichloromethane	Antimony 125
1,2-Dichloropropane	Cobalt 58
cis-1,3-Dichloropropene	Cobalt 60
Trichloroethene	Cerium 144
Dibromochloromethane	Ruthenium 103
1,1,2-Trichloroethane	Ruthenium 106
Benzene	Cesium 134
trans-1,3-Dichloropropene	Cesium 137
Bromoform	Strontium 90
4-Methyl-2-pentanone	Uranium 234
2-Hexanone	Uranium 235
Tetrachloroethane	Uranium 238
Toluene	Iodine 129
1,1,2,2-Tetrachloroethane	
Chlorobenzene	
Ethyl Benzene	
Styrene	
Xylenes (total)	

contractor was responsible for recovery, preservation, and storage of all samples until delivery to the laboratory for analysis. Drilling operations were conducted by the drilling subcontractor, Hawley Brothers Drilling of Blackfoot, ID.

Soil samples were analyzed by Pacific Northwest Environmental Laboratory, Inc. of Redmond, Washington, for the constituents shown in Table 1 (except for radionuclides). Fracture fillings from the deep borehole were analyzed by MetaTRACE, Inc. of St. Louis, Missouri for all Table 1 constituents including radionuclides. The 0 - 6 foot samples from borehole 6 were split and analyzed at Gulf Southern Environmental Laboratory, Inc. of New Orleans, Louisiana and by Southwest Laboratory of Oklahoma, Inc of Tulsa, Oklahoma, for dioxins and furans only. Radionuclides were analyzed for only after discovery of the contamination in the deep borehole.


## 5.1 Unit Sampling

### 5.1.1 Sampling Locations

Eleven boring locations were randomly selected from the intersection points of a 10' x 10' grid (see Figure 4). Random sampling was deemed appropriate in that the discharges were small quantities over a potentially broad area. Ten borings were continuously cored to a depth of 6 feet and one boring was cored to a depth of approximately 103 feet. The 6 foot depth was chosen as a maximum depth in that the amounts discharged were small, and the possible contaminants potential for migration was negligible, since there is little hydraulic driving force.

### 5.1.2 Drilling

All shallow drilling was conducted between December 19, 1989 and January 5, 1990. The drilling operation for the deep borehole was conducted from February 6 to February 22, 1990. Borehole logs are presented in Appendix B.



#### Explanation

- Randomly selected shallow borehole locations located at the intersections of a 10' x 10' grid. Total depth = 6'
- ⊕ 110' borehole, location at 14'S, 32'W, from SE corner of Building T-15. Total depth = 122.9'

FIGURE 4.  
SAMPLING LOCATIONS AND  
BOREHOLE NUMBERS  
LAND DISPOSAL UNIT CPP-55  
EG&G/ICPP/ID

All drilling was conducted using a Central Mining Equipment model 55 drill rig. Surface soils were drilled utilizing a 4" inside diameter (ID) hollow stem auger. An aluminum pan was placed around the augers to facilitate sample collection and prevent the spread of any contamination to the surrounding soil. Soil samples were collected using a 24 inch long x 4" outside diameter (OD) California split-spoon sampler driven ahead of the auger flight by a rig-mounted, cat-head operated 140 lb hammer. The number of hammer blows, for each six inches of sampler advancement, was recorded by the field geologist. Upon completion of sampling, each borehole was backfilled with clean native soil. As a precaution all waste drill cuttings were placed in 55 gallon DOT approved drums and shipped off site to a RCRA approved facility (USPCI of Murray, UT) for final disposal.

The deep borehole was drilled by first augering through the surface sediments with the 4" ID auger to the top of the basalt, approximately 44 feet. At that time, a temporary 6 inch casing was installed and coring continued into the bedrock using a CP series wireline coring device. Coring continued until the total depth of approximately 123 feet was reached. All sediment and basalt samples were collected in clear lexan inner liners used in the sampling devices.

During routine health physics (HP) surveying of the drilling site and cores, unexpected radiologic contamination was detected in rock cores while drilling the deep borehole. The 5" borehole was not backfilled, but was instead converted to a 2" monitoring well following procedures as outlined in the RCRA Technical Enforcement Guidance document. Appendix B contains the boring log and well construction diagram for this unit. Further evaluation of this radiologic contamination is ongoing and will be addressed as a separate issue under the INEL Interagency Agreement.

### 5.1.3 Sampling Methods

As a result of frozen ground, only boring 55-01 was continuously cored utilizing a split-spoon sampler for the entire depth. All other borings sampled the 0 - 2 foot level by taking a grab sample of the material as it came off the auger flight into the aluminum pan. Below two feet all sediment samples were collected by driving the split-spoon sampler in 2 foot increments as outlined above. Adjacent to borehole CPP-55-05 a second borehole was used to collect the 0 - 2 foot sample, as a result of split-spoon refusal in the first borehole. Also, a second borehole labeled CPP-55-2A was needed after the split-spoon sampler encountered refusal at 2.7 feet in borehole CPP-55-02.

All samples were collected within a 24 inch clear lexan inner liner placed in the split-spoon. Once removed from the borehole, the sampler was placed on clean plastic sheeting and opened. The open ends of the lexan tube were scanned for beta-gamma radiation with all instrument readings recorded by the field geologist. The tube was then sealed and the soils logged. Once the sample was logged it was handed out of the exclusion zone set up around the drill rig for sample preparation. All soil sampling was conducted in accordance with the sampling contractors Technical Procedure TP1.2-5, "Drilling, Sampling, and Logging of Soils" (Golder 1990a). Furthermore, all samples were handled within the chain-of-custody procedures specified in TP-1.2-23 (Golder 1990a).


Sample preparation was conducted by the sampling subcontractor outside of the exclusion zone. In the sample prep area the lexan tube was opened and 2 to 4 inches of material from the top of the sample were removed and discarded. Samples collected for mineral spirits, semi-volatile, and volatile organic analyses were then immediately transferred into appropriate sample containers. Contact time with the lexan sampling liner was never more than 15 minutes, prior to sample removal. For this reason the possibility

of cross contamination of organics is considered negligible. The remaining sample was homogenized, by mixing with a stainless steel rod in a stainless steel bowl, with a sub-sample being placed in an 8 ounce plastic sample container for inorganic analysis. Excess sample material was disposed of into WINCO managed waste containers. All sample containers were sealed with teflon lined lids and placed in a 4°C cooler for preservation prior to shipment to the appropriate laboratory. Grab samples from the 0' - 2' interval were placed directly into sample containers.

Deep borehole cores were collected in 5 foot lengths also within clear lexan liners. Upon removal from the borehole the lexan tube was sealed and logged in accordance to Technical Procedure TP-1.2-2, "Geotechnical Rock Core Logging" (Golder 1990a). These samples were handled under the same chain-of-custody procedure as the soil samples. Samples of fracture fillings were taken by uncapping the lexan tube, carefully extruding the core from the lexan tube, and scraping material into sample containers. The excess core was placed back in the lexan tube, sealed, and is archived at the ICPP.

## 5.2 Background Sampling

Ten background samples were collected in 1986 by the University of Utah Research Institute (UURI), Salt Lake City, UT., during two unit characterization studies (SWMU CPP-46 at the Chemical Storage and Zirconium Feed Storage Tank area and SWMU CPP-53 at the FPR Warehouse site). The background samples were collected from seven sample locations outside of the ICPP security fence (see Figure 5). Samples were collected at surface and at 6, 18, and 24 inches. All background samples were collected and analyzed using EPA methods. UURI's report stated that the soils taken from the background locations were geologically identical to the native soils in the sampling areas within the ICPP.



Samples and background samples collected for the FPR Warehouse Site (Bkg 1-4) were analyzed for the same hazardous constituents that were analyzed for during this unit characterization. Background samples collected for the Chemical Storage and Zirconium Feed Tank Storage Areas (258-265) were analyzed for pH, nitrates, aluminum, zirconium and heavy metals. The pertinent background sample results are shown in Table 2.

Since all background samples were collected adjacent to the ICPP and all sampling and analyses were conducted using EPA methods, the results will be used as a comparison with the shallow soil sample characterization data from this report. Section 5.7.2 discusses limitations on this data.

### 5.3 Quality Assurance Samples

Quality assurance samples submitted for LDU CPP-55 included eight trip blanks, three equipment blanks, three field blanks, four field duplicates, two decontamination rinseate, and one blind sample. Results of the quality assurance sample analyses are presented in Appendix C. Equipment blanks were prepared by collecting the final rinse water from the decontamination procedure described below. Field blanks were made utilizing the deionized water used for decontamination purposes. Field duplicates were made by splitting an original sample from a selected depth. The blind sample was prepared by spiking commercially available distilled water with an EPA quality control reference sample. Decontamination rinseate samples were collected from the decon trough prior to pumping into 55 gallon drums.

All quality assurance samples were analyzed using the same EPA approved methods as for soil samples and as outlined by the sampling subcontractors Quality Assurance Program Plan (Golder, 1990c). This QAPP was developed in accordance with NQA-1 and QAMS-005 guidance.



Table 2.

Background Concentrations of Metals in Soils Sampled from Outside the ICPP Facility and One-Sided Normal Tolerance Intervals <sup>1</sup>								
BACKGROUND SAMPLE	RESULTS IN PPM							
Sample	Arsenic	Barium	Cadmium	Chromium	Lead <sup>2</sup>	Mercury	Selenium	Silver
Bkg 1	5.6	200	<5	25	12	0.043	0.484	<2
Bkg 2	5.1	270	<5	32	16	0.019	0.405	<2
Bkg 3	6.5	270	<5	33	17	0.027	0.467	<2
Bkg 4	7	250	<5	34	12	0.028	0.341	<2
258	5.6	280	<5	28	<10	0.025	0.113	<2
259	7.6	380	<5	26	<10	0.057	0.252	<2
260	6.4	240	<5	28	<10	0.023	0.695	<2
261	6.2	220	<5	18	<10	0.03	0.236	<2
264	6	230	<5	28	<10	0.021	0.102	<2
265	7.6	210	<5	20	<10	0.046	0.227	<2
Maximum	7.6	380	<5	34	17	0.057	0.695	<2
Minimum	5.1	200	<5	18	<10	0.019	0.102	<2
Average	6.4	255	<5	27	9	0.032	0.332	<2
Std. Dev. (SD)	0.8	51	--	5	5	0.013	0.184	--
Background UTI <sup>3</sup>	8.7	403	--	42	24	0.070	0.868	--

1. All analyses are total constituent analyses, using EPA approved methods, and are reported on a weight per dry basis. Samples Bkg 1 - 4 were from the FPR Warehouse site (SWMU CPP-46); samples 258 - 265 were from the Zirconium Feed Storage Tank site (SWMU CPP-53).
2. Where lead values are listed below detection limit, a value of one-half the detection limit was used in the calculation of the average standard deviation and tolerance limit values.
3. The background one-sided upper tolerance interval (UTI) is  $x + K \cdot SD$ , where the K value (tolerance factor) for sample size  $n = 10$  is equal to 2.911 with a probability level  $y = 0.95$  and coverage  $P = 0.95$ .

#### 5.4 Radiation Survey

Radiation surveys were conducted by a WINCO Occupational Health Physicist (OHP) in accordance with WINCO Standard Operating Procedures (SOPs). A routine radiation survey of the drilling equipment was made prior to the rig entering or leaving the ICPP secured area. Radiation surveys were also conducted at the unit prior to commencing any sampling activities. All sediment samples were surveyed for direct radiation prior to removing samples from the unit. All instrument measurement results were logged in the Field Log Book by the field geologist.

Direct radiation was measured using Geiger-Mueller detection tubes, which were calibrated and used for the purpose of health protection and locating any radioactive "hot spots" within samples. The instruments were calibrated by the WINCO instrument laboratory prior to field use. Any field instrument used was operated by a trained radiation Operational Health Physicist (OHP) to ensure the safety of field and sampling personnel.

#### 5.5 Sample Preservation Methods and Holding Times

Samples were not chemically preserved, however they were refrigerated at approximately 4°C. The samples were shipped in coolers and kept cooled until analysis. Any time sensitive soil sample analyses (e.g., those for volatile and extractable organics) were extracted within 7 to 14 days. All other analyses were conducted within the required 28 day limit.

## 5.6 Sample Packing and Shipping

The packing and shipping of soil samples containing hazardous substances is regulated by the Department of Transportation (DOT). All sample containers shipped were classified as environmental samples as required by the DOT. These were packed in a sealed shipping cooler surrounded by an inert packing material (vermiculite), a cooling agent ("blue ice"), a trip blank, and chain-of-custody documentation (Golder 1990a).

## 5.7 Data Validation, Evaluation, and Reporting

### 5.7.1 Data Validation

All analytical data was reviewed using EPA CLP equivalent methods, to ensure that the analytical laboratories met their requirements as outlined in the Technical Work Plan, (Golder, 1990a). In general, validation included a review of:

- sample receipt tracking documentation;
- instrument calibration documentation;
- quality control data;
- analytical results and/or data deliverables.

The specific requirements for the validation of data from unit LDU CPP-55 can be found in Volume II, Section 8 of the Technical Work Plan (Golder, 1990a).

MetaTRACE was employed for analysis of soil samples associated with fracture fillings at LDU CPP-55. The work performed by MetaTRACE included organic, inorganic, radionuclide and 40 CFR 261, Appendix VIII hazardous constituent analyses. This laboratory was already under contract with the sampling subcontractor, prior to being suspended from the EPA contract laboratory program (CLP) in March 1990. WINCO believes that the analytical work conducted by MetaTRACE is valid and defensible. Our reasons are as follows:

- MetaTRACE was assessed by the sampling subcontractor in compliance with ANSI/ASME NQA-1 QA program requirements through onsite evaluation prior to contract award.
- All of MetaTRACE's analytical results were subjected to rigorous independent validation in compliance with WINCO - approved validation protocols based on those used by the EPA in its CLP.
- The sampling subcontractor introduced blind performance audit samples into the samples delivered to MetaTRACE; all performance audit sample results were within the EPA-defined control limits.
- The sampling subcontractor conducted a laboratory surveillance at MetaTRACE on March 22, 1990, with WINCO QA, technical, and project management representatives observing. MetaTRACE was observed to have initiated corrective action measures related to the problems specified in the EPA directive.

The results of data validation indicate that all time sensitive soil sample analyses (i.e., those for volatile and extractable organics) were extracted within EPA specified holding time limits. All other analyses were conducted within the required 28 day limit. Holding times for organic analyses of soils have yet to be established, but the most recent proposed update to SW-846 recommends all soils, sediments, and sludges be analyzed within 14 days (EPA 1987).

Initial results of the analysis for mineral spirits reported levels above detection limits. However, upon undergoing validation procedures, were eliminated from consideration due to contamination found in all associated laboratory blanks. As part of the validation a review of the chromatograms for all mineral spirits revealed a substantial rise in the baseline. This was quantified by the laboratory as an indication of the presence of mineral spirits. Validation review determined the rise to be a false identification of an interfering contaminant, and thus eliminated all mineral spirits data from further consideration.

Organic compounds (toluene, 4-methyl 2-pentanone, and bis (2-ethylhexyl) phthalate) were detected and validated in some soil samples. These are all recognized as common laboratory contaminants and were found near or below the sample detection limits. Comparison of these compounds with results from the associated blanks and using the criteria and rationale as specified in Part XI of the EPA data validation guidelines (EPA 1988b) eliminated them from further consideration.

#### 5.7.2 Data Evaluation

Background levels were determined from samples collected by the University of Utah Research Institute (UURI), Salt Lake City, Utah, during two studies conducted in 1986 and 1987. Ten background samples were collected outside the ICPP fence from the surface to a depth of 24 inches. A summary of this data is presented in Table 2. Also shown on this table is the one-sided upper tolerance interval (UTI) for the background data, assuming a normal distribution with 95% coverage of samples at a 95% confidence coefficient. A UTI is a concentration range, from background data, in which a large portion of the background observations should occur with a high probability. There are a number of caveats to the use of the UURI data for determining "action" levels to trigger cleanup activities. These limitations include:

- all UURI data is from the near surface (0" - 24") level and may not be representative of deeper soils;
- many areas of the ICPP have been graded or filled. Background samples collected by UURI represent native material and may not be representative of this fill material;
- certain constituents are elevated above natural background as a result of point and non-point sources as a result of site activities. It would be inappropriate to establish cleanup levels based on natural background if there is

widespread elevation of constituent concentrations not associated with releases from the LDU.

Organic constituents were evaluated to determine their presence above sample quantification limits. Inorganic results were evaluated to determine their presence above a listed background UTI (see Table 2).

If an inorganic analysis resulted in a concentration above the upper threshold interval (UTI), it was screened for EP-Toxicity leaching using an upper threshold limit (UTL). This UTL was used to determine if a sample approached a regulatory limit. Based on the required diluting of a sample, by a factor of 20, for conducting an EP-Toxicity leach test, the total constituent analyses threshold limits were established as the EP-regulatory threshold times 20. Therefore, if a sample exceeded its corresponding UTI, it was further screened to see if it exceeded its UTL. If the sample also exceeded its UTL, it was subjected to an EP-Toxicity leach test. More simply stated, if a constituent was detected above the background level (UTI) it was further evaluated to determine if it was above a derived regulatory threshold (UTL). If it was also above this threshold then a sample was subjected to an EP-Toxicity leach test. The EP-Toxicity results were then compared to the regulatory limit. Should the result be above the regulatory limit, then the material was considered a RCRA hazardous waste.

Analyses and screening showed that only five inorganics (arsenic, chromium, lead, mercury, and silver) and three organics (toluene, 4-methyl 2-pentanone, and bis (2-ethylhexyl) phthalate) were detected above their UTIs. Of these, only one mercury sample exceeded the UTL and was tested for EP-Toxicity. Analysis of the leachate from this test did not detect any mercury. The organics detected were all eliminated from further consideration during validation procedures (see Section 5.7.1).

### 5.7.3 Data Reporting

All data was reported to the sampling subcontractor in both their reduced and raw forms. Concentration values were presented with their appropriate units of measure and uncertainty values. Data, as presented to WINCO in the attached final report, was in its reduced form only. Therefore, the data as presented in this document, is given in its reduced form. Raw data information is available upon written request.

## 5.8 Sample Analysis

All soil samples were analyzed for the constituents shown in Table 1, except for radionuclides at Pacific Northwest Environmental Laboratory, Inc. of Redmond, Washington. Fracture fillings from the deep borehole were analyzed by MetaTRACE, Inc. of St. Louis, Missouri for all Table 1 constituents including radionuclides. The 0 - 6 foot samples from borehole 6 were split and analyzed at Gulf Southern Environmental Laboratory, Inc. of New Orleans, Louisiana and by Southwest Laboratory of Oklahoma, Inc. of Tulsa, Oklahoma, for dioxins and furans only. Radionuclides were not an original target analyte. They were added to the list and analysis only after discovery of the radiologic contamination in the deep borehole. Additional information associated with the sample collection and analysis can be found in the Technical Work Plan (Golder, 1990a).

### 5.8.1 Chemical/Radiological Sample Analysis

All samples were analyzed for hazardous constituents using EPA approved methods (SW-846). Analysis results were documented and validated using CLP equivalent methods following EPA data validation guidelines (EPA 1988a and 1988b).

Sample analyses were conducted on all soil samples from boreholes 1 through 5 and 7 through 11 for the constituents listed in

Table 1, except for the radionuclides. The soil samples from borehole 6 from the surface to 6 feet were analyzed for 40 CFR part 261 Appendix VIII parameters, Target Compounds List analytes not found under Appendix VIII, and radionuclides (see Appendix D). Samples from 6 feet to top of bedrock, were analyzed for Table 1 constituents with the exception of radionuclides and mineral spirits. Fracture fillings, from borehole CPP-55-06 were analyzed for all Table 1 parameters.

Of the inorganic constituents analyzed for only arsenic, chromium, lead, silver, and mercury exceeded their respective upper tolerance intervals (UTI) (see Section 5.7.2 for a description of the UTI). There is no apparent correlation between location of the elevated concentrations and depth of collection (see Table 3).

Arsenic and chromium exceeded their UTIs in only one sample each from two different boreholes, CPP-55-07 the 2' - 4' interval and CPP-55-11 the 4' - 6' interval, respectively. Lead exceeded the UTI in two samples, 0' - 2' and 2' - 4', from two different boreholes, CPP-55-05 and CPP-55-08, respectively. Silver exceeded the UTI in a number of samples, but never by more than 1 mg/kg. Furthermore, as a result of the statistical method utilized, the UTI for silver is artificially set at the detection limit. Thus, any silver detected would be above its UTI level. This was required in that all background UTIs for silver were below the current sample detection limit. To have used half the UTI in statistical methods would have yielded invalid results. The methodology incorporated was done in accordance with EPA approved methods. None of these metals approached their respective upper threshold limits (see Section 5.7.2 for discussion of upper threshold limit).

Mercury was the only inorganic constituent detected in more than two samples. It was detected from at least one depth in all but one borehole, CPP-55-01. The 0 - 2 foot sample generally contained the



Table 3.  
Inorganic Sample Analysis Results  
Land Disposal Unit CPP-55

Borehole	Depth	Arsenic mg/Kg	Barium mg/Kg	Cadmium mg/Kg	Chromium mg/Kg	Iron mg/Kg	Lead mg/Kg	Mercury mg/Kg	Nickel mg/Kg	Selenium mg/Kg	Silver mg/Kg
CPP55-01	0' - 2'	4.7	215.0	1.00 U	24.5	17,900	13.0	0.05 U	20.0	0.620 U	2.9
	2' - 4'	5.1	70.0	1.00 U	28.5	10,500	6.3	0.05 U	16.3	0.580 U	2.0 U
	4' - 6'	4.7	91.2	1.00 U	21.6	10,600	6.3	0.05 U	17.4	0.570 U	2.0 U
CPP55-02	0' - 2'	6.2	144.0	1.00 U	32.4	13,900	10.6	0.12	21.8	0.620 U	2.1 U
	2' - 4'	6.1	133.0	1.00 U	29.6	12,900	10.1	0.27	19.1	0.610 U	2.0 U
	4' - 6'	5.5	96.1	0.90 U	15.2	10,600	7.6	0.05 U	16.8	0.560 U	1.8 U
CPP55-03	0' - 2'	7.3	115.0	1.00 U	38.8	12,500	10.5	0.09 B	19.6	0.610 U	2.0 U
	2' - 4'	4.9	120.0	1.00 U	24.4	12,800	7.8	0.45	17.0	0.540 U	2.0 U
	4' - 6'	5.1	120.0	1.00 U	29.5	10,900	5.8	0.07 B	21.4	0.600 U	2.1 U
CPP55-04	0' - 2'	6.7	140.0	1.00 U	23.3	14,000	11.9	0.65	22.6	0.640 U	2.1 U
	2' - 4'	6.0	134.0	1.10 U	19.7	12,800	9.7	0.42	20.6	0.620 U	2.1 U
	4' - 6'	5.9	117.0	0.98 U	22.8	14,400	16.7	0.20	24.4	0.610 U	2.0 U
CPP55-05	0' - 2'	5.7	183.0	1.00 U	32.6	17,100	10.1	0.19	24.3	0.580 U	3.0
	2' - 4'	5.0	97.4	1.00 U	23.1	11,600	32.0	0.05 U	18.1	0.520 U	2.1
	4' - 6'	4.7	86.2	1.00 U	23.8	9,680	6.8	0.12	17.9	0.580 U	2.0
CPP55-06	0' - 2'	4.9	109.0	1.1	16.4	NA	8.9	0.11	20.4	0.410 U	0.5 U
	2' - 4'	5.0	88.9	0.99 U	13.3	NA	9.0	0.20	16.8	0.400 U	0.5 U
	4' - 6'	6.4	164.0	1.4	20.9	NA	8.6	0.22	27.6	0.400 U	0.7 U
CPP55-07	0' - 2'	5.6	134.0	1.00 U	21.8	13,000	8.4	0.58	18.6	0.610 U	2.1
	2' - 4'	13.4	106.0	1.00 U	21.1	11,800	9.6	0.05	17.5	0.530 U	2.0 U
	4' - 6'	8.0	82.0	1.00 U	15.8	8,660	14.5	0.05	16.0	0.500 U	2.0 U
CPP55-08	0' - 2'	6.5	138.0	0.98 U	25.4	15,100	28.7	0.08 B	65.0	0.630 U	2.0 U
	2' - 4'	6.1	134.0	0.90 U	25.3	15,100	7.9	0.05 U	22.2	0.590 U	1.9
	4' - 6'	6.1	95.3	0.87 U	21.2	13,100	6.9	0.05 U	18.7	0.600 U	1.7 U
CPP55-09	0' - 2'	8.0	163.0	0.99 U	40.5	18,100	11.0	0.13	26.5	0.590 U	2.0 U
	2' - 4'	7.1	134.0	0.94	20.9	14,300	10.7	0.05 U	18.8	0.630 U	1.9 U
	4' - 6'	6.2	108.0	1.00 U	17.9	12,100	7.2	0.05 U	18.1	0.570 U	2.0 U
CPP55-10	0' - 2'	4.7	181.0	1.00 U	29.9	17,200	9.0	0.49	24.1	0.560 U	2.3
	2' - 4'	6.2	160.0	1.00 U	29.5	16,300	10.4	0.11	23.9	0.560 U	2.5
	4' - 6'	6.0	88.2	1.00 U	18.3	11,300	6.3	0.05 U	16.0	0.560 U	2.0
CPP55-11	0' - 2'	5.2	148.0	1.00 U	25.1	14,500	9.7	5.20 *	21.5	0.530 U	2.4
	2' - 4'	3.8	133.0	1.00 U	26.4	16,100	6.9	0.05 U	25.4	0.600 U	2.4
	4' - 6'	4.4	105.0	1.00 U	64.7	11,500	6.1	0.05 U	20.2	0.570 U	2.1 U
Maximum value		13.4	215.0	1.40	64.7	18,100	32.0	5.20	65.0	0.640 U	3.0
Minimum value		3.8	70.0	0.87 U	13.3	9,680	5.8	0.05 U	16.0	0.400 U	0.5 U
Detection limit		3.0	10.0	1.00 U	10.0	50	3.0	0.05	20.0	0.500	2.0
Bkgnd UTI		8.7	403.0	5.00	42.0	—	21.0	0.07	—	0.870	2.0

U = compound was analyzed for but not detected, the reported value is the sample detection limit.

\* = result is the average of three analyses, 7.1, 5.7 and 2.8 mg/Kg.

highest concentrations at most sampling sites. Only one sample, 0' - 2', from CPP-55-11 contained concentrations above both the UTI and the test no mercury was detected (see Table 4). This single sample is from one of the locations farthest from the potential discharge source upper threshold limit. When subjected to the required EP-Toxicity leach (building T-15). Since the reported value is the average of three widely varied analytical results, the concentration vs distance is probably related more to some heterogeneity in the soil than to a discrete disposal event. This is further supported by the fact that only this sample at this location was above detection limits.

Three organic constituents, toluene, 4-methyl 2-pentanone, and bis (2-ethylhexyl) phthalate were detected from the volatile organic analyses (see Table 5). During validation procedures all were eliminated from further consideration as they are all recognized laboratory contaminants as illustrated in Section 5.7.1 of this report and Section 3.3 of (Golder, 1990c). Furthermore, concentrations of toluene and 4-methyl 2-pentanone were detected near or below detection limits (5 and 10 ug/kg respectively). Bis (2-ethylhexyl) phthalate, though above detection limits, was also found in associated laboratory blanks.

Deep soil samples (below 6 feet) were not evaluated against UTIs because of the shallow depth of the background samples. They were, however, screened against their derived upper threshold limit (UTL). In general, the concentrations were higher the deeper the sample collection depth. Table 6 lists the concentrations found in the deeper soils. It should be noted that no metals exceeded their respective UTLs.

Radioactive contamination, mainly strontium-90, was detected at significant levels in the deeper fracture fillings within the basalt, and in lower concentrations in the perched water. For this reason the borehole CPP-55-06 was converted to a 2" RCRA monitor well. Since there is no potential source and no evidence of strontium release at the surface, this contamination is thought to have migrated laterally from a

Table 4.

Borehole: CPP-55-11 Depth: 0' to 2'				
Analytical Parameter	Total Results (mg/Kg)	Threshold Limit (UTL) (mg/Kg)	EP-Toxicity Results (mg/Kg)	Regulatory Limit (mg/L)
Arsenic	5.2	100	0.003 u	5.0
Barium	148	2000	1.194	100.0
Cadmium	1.0 u	20	0.005 u	1.0
Chromium	25.1	100	0.01 u	5.0
Lead	9.7	100	0.003 u	5.0
Mercury	5.2*	4	0.0001 u	0.2
Selenium	0.53 u	20	0.003 u	1.0
Silver	2.4	100	0.01 u	5.0

u = signifies the compound was analyzed for but not detected. The listed value is the sample detection limit.

\* = signifies the result is an average of three consecutive measurements of 7.1, 5.7, and 2.8 mg/Kg.

UTL is described in text section 5.7.2.

Regulatory Limit refers to EP-Toxicity characteristic limit as specified in 40 CFR Part 261.24, Table I.

Table 5.

Organic Sample Analysis Results					
Borehole	Depth (ft)	4-Methyl-2-Pentanone ug/Kg	Toluene ug/Kg	Bis(2-ethylhexyl)-phthalate ug/Kg	High Boiling Point Hydrocarbons mg/Kg
CPP55-01	0 - 2	10u	1j	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-02	0 - 2	10u	3j	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-03	0 - 2	10u	5u	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-04	0 - 2	10u	5u	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-05	0 - 2	10u	5u	330u	440
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-06	0 - 2	15	5u	1800	NA
	2 - 4	10u	5u	4000	NA
	4 - 6	10u	5u	330u	NA
CPP55-07	0 - 2	10u	5u	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-08	0 - 2	10u	5u	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-09	0 - 2	10u	5u	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-10	0 - 2	10u	5u	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
CPP55-11	0 - 2	10u	5u	330u	NA
	2 - 4	10u	5u	330u	NA
	4 - 6	10u	5u	330u	NA
Maximum value		15	5u	4000	440
Minimum value		10u	3j	330u	NA
Detection limit		10	5	330	NA

u = compound analyzed for but not detected, the reported value is the sample detection limit.

j = indicates an estimated value. Used when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed, or when the mass spectral data indicate the presence of a compound that meets the identification criteria but the result is less than the sample detection limit but greater than zero.

High boiling point hydrocarbons were determined by GC/FID (Modified EPA Method 8015/CDOHS method).

Table 6															
Inorganic and Radiochemical Analysis Results (mg/Kg or pCi/g)															
Borehole 6, Land Disposal Unit CPP-55															
Borehole	Depth	Arsenic	Barium	Cadmium	Chromium	Iron	Lead	Mercury	Nickel	Selenium	Silver	Strontium 90		Potassium 40	
CPP55-06	0' - 2'	4.9	109.0	1.10	16.4	NA	8.9	0.11	20.4	0.410 U	0.5 U	NA		NA	
	2' - 4'	5.0	88.9	0.99 U	13.3	NA	9.0	0.20	16.8	0.400 U	0.5 U	NA		NA	
	4' - 6'	6.4	164.0	1.40	20.9	NA	8.6	0.22	27.6	0.400 U	0.7 U	NA		NA	
A L L U V I U M	6' - 8'	5.9	141.7	1.01 U	21.4	11,200	6.6	0.14	22.7	0.550 U	2.0 U	NA		NA	
	8' - 10'	12.1	115.1	1.06 U	20.1	11,820	6.9	0.30	24.6	0.610 U	2.1 U	NA		NA	
	10' - 12'	5.9	98.5	1.02 U	16.0	7,674	7.5	0.05 U	14.6	0.550 U	2.0 U	NA		NA	
	16' - 18'	5.4	122.9	1.03 U	15.1	9,473	9.0	0.05 U	13.8	0.550 U	2.1 U	NA		NA	
	20' - 22'	6.6	136.9	0.88 U	23.9	11,400	7.2	0.05 U	19.8	0.620 U	1.8 U	NA		NA	
	24' - 26'	5.6	125.7	0.98 U	21.8	11,970	6.0	0.05 U	21.6	0.580 U	2.0 U	NA		NA	
	28' - 30'	6.5	133.7	0.88 U	17.6	10,790	6.8	0.05 U	17.5	0.530 U	1.8 U	NA		NA	
	32' - 34'	6.0	114.8	1.00 U	17.7 U	10,690	6.8	0.04 U	16.8	0.620 U	2.0 U	NA		NA	
	36' - 38'	6.5	117.2	0.98 U	18.7	10,220	6.7	0.05 U	15.5	0.570 U	2.0 U	NA		NA	
BASAL CLAY	40' - 42'	8.4	223.1	1.10 U	35.5	22,190	14.7	0.05 U	32.2	0.640 U	2.2 U	NA		NA	
	42' - 44'	10.0	238.6	1.10 U	41.5	22,330	15.8	0.06 U	35.4	0.590 U	2.2 U	NA		NA	
FRAC. FILL	111'	7.6	426.0	0.70 U	13.8	46,365	8.1	0.10 U	100.0	0.700 U	6.0	4800	500	14	2
FRAC. FILL	115'	5.2	398.0	0.70 U	27.6	49,174	8.0	0.10 U	121.0	0.700 U	6.1	4300	500	16	2
INTERBED	117'	7.9	609.0	0.80 U	36.0	21,953	4.1	0.10 U	52.6	0.800 U	2.9	1	U	28	3
INTERBED	119'	7.4	295.0	1.20	31.1	25,226	5.0	0.10 U	48.6	0.600 U	3.8	1	U	29	3
INTERBED	121'	6.6	359.0	0.80 U	33.0	27,098	5.9	0.10	51.0	0.800 U	3.6	1	U	28	3
Maximum value		12.1	609.0	1.40	41.5	49,174	15.8	0.30	121.0	0.800 U	6.1	4800		29	U
Minimum value		4.9	88.9	0.70 U	13.3	7,674	4.1	0.04 U	13.8	0.400 U	0.5 U	4300		14	
Detection Limit		3.0	10.0	1.00	10.0	50	3.0	0.05	20.0	0.500	2.0	1 U		1	

U = Compound was analyzed for but not detected the associated value is the sample quantitation limit.

separate source, and, as such, will be treated separately from the issue of CPP-55.

#### 5.8.2 Quality Assurance Sample Analysis

The quality of sample data is of utmost importance. Quality assurance/quality control (QA/QC) procedures were implemented throughout the collection and analysis of samples. QA/QC procedures utilized during the chemical analysis portion of this program consisted of the following:

- analysis of trip, equipment, and field blank samples for monitoring of potential contamination introduced from the sampling containers, decontamination process, or the shipping containers;
- analysis of field duplicate samples for the measurement of overall field and laboratory precision;
- analysis of blind reference samples for volatile organics and selected trace metals;
- analysis of decontamination rinseate for characterization and determination of disposal requirements;
- a procedure audit was conducted at the sampling site during routine sample collection and
- an analysis audit was preformed at one of the contract laboratory facilities to track handling and analysis of samples.

All QA samples were analyzed by the same methods used for the soil samples. Results of the QA sample analyses are listed in Appendix C.

## 6. CLOSURE PROCEDURES

Section 5 of the approved closure plan stated that "If the unit is contaminated above RCRA regulatory thresholds, the unit will be clean-closed". Since none of the detected constituents were above RCRA regulatory thresholds for EP-Toxicity and no listed waste were detected, this unit will not require removal action to obtain clean closure and can be safely eliminated as a hazardous site.

The concentrations of the constituents were also below the risk based action levels listed in the proposed RCRA corrective action guidelines (Federal Register Vol. 55, No. 145, pp 39798-30884). Furthermore, a Health and Environmental Assessment of the unit (see Appendix A) showed that the highest risk factor to be from ingestion of chromium contaminated soil (at  $1.3 \times 10^{-5}$  for a residential adult scenario). Risk associated with the most wide spread contaminant found, mercury, is at the  $1.0 \times 10^{-6}$  level for the same scenario. Since the site is located within a fenced security area that is anticipated to continue operations well into the next century, the use of the residential scenario is very conservative.

## 7. DECONTAMINATION PROCEDURES

Prior to use, all split-spoon samplers, lexan liners, and associated sampling equipment were decontaminated by the sampling subcontractor. Decontamination is specified in Section 5 of the attached Technical Work Plan and consisted of:

- steam cleaning equipment with deionized water;
- drying, then wiping with a methanol dampened rag;
- air drying and a final rinse with deionized water;
- wiping dry and wrapping in clean, fresh plastic until needed.

The drill rig was decontaminated by the drilling subcontractor, under direction of the sampling subcontractor, before moving on site. Decontamination consisted of high pressure steam cleaning at a site designated by WINCO personnel. After steam cleaning sampling personnel visually inspected the rig for signs of grease, hydraulic fluid, or other potentially

contaminating materials. A routine radiation survey was also conducted prior to the rig entering and leaving the ICPP secured area.

Decontamination rinseate from the washing of the sampling equipment was collected in a decon trough. Samples of this rinseate were collected prior to pumping out the trough and analyzed for proper disposal. Rinseate was pumped from the trough into 55 gallon DOT approved drums, for storage and disposal, after sampling.

#### 8. POST-REMOVAL SAMPLING AND ANALYTICAL PROCEDURES

Since LDU CPP-55 is being presented for clean closure without removal, post-removal sampling and verification will not be required. If, under the upcoming INEL Interagency Agreement, further action is deemed necessary, it will be addressed at that time.

#### 9. CLOSURE QUALITY ASSURANCE/ QUALITY CONTROL PROCEDURES

All administrative, sampling, and analysis activities were performed in accordance with sound QA/QC procedures. These procedures are outlined in the Quality Assurance Program Plan: INEL/ICPP Land Disposal Unit Characterization Support (Golder Assoc., 1990c) and the Quality Assurance Project Plan for Drilling and Sampling at Land Disposal Units CPP-34 and CPP-55 (Golder Assoc., 1990a). These plans meet the requirements for proper QA program controls by incorporating all applicable sections of ANSI/ASME NQA-1, Quality Assurance Program Requirements for Nuclear Facilities, and EPA's Interim Guidelines for Preparation of Quality Assurance Project Plan, QAMS/005.



#### 10. CLOSURE CERTIFICATION

Since LDU CPP-55 is to be clean closed without removal, closure certification may not be required. If deemed necessary this certification will be provided to verify that sampling was done in accordance with the procedures outlined in the approved closure plan.

#### 11. AREA RESTORATION

Since no remedial actions are anticipated for this site, area restoration will not be required. If future activities are preformed at this site, restoration concerns will be addressed at that time. All drilling spoils were containerized and disposed of under ICPP waste management procedures.

#### 12. OTHER TOPICS OF CONCERN

At this time, based on regulatory limits and health and environmental assessments there are no other concerns dealing with this unit. The radioactive contamination found from 69 feet to 119 feet in the deep borehole is to be investigated further as characterization of the 110 foot interbed is carried out.

#### 13. SCHEDULE OF ACTIVITIES

This document is being submitted to EPA Region X and the State of Idaho for final approval of the closure plan submitted in January 1989 and approved in September of 1989.

#### 14. POST CLOSURE

Since the hazardous constituents detected were all below regulatory concerns and do not pose any unacceptable risk to human health or the environment, post closure requirements under RCRA (40 CFR 265.117 - 120) and the Consent Order and Compliance Agreement will not be required for this unit.

Future activities deemed necessary under the upcoming INEL Interagency Agreement may require post closure monitoring. The ICPP is currently developing a detailed facility wide Groundwater Monitoring Plan as required under 40 CFR 265.90 to address all units.

## 15. REFERENCES

- Cooper, S. C., Geological and Hydrological Characterization of the Idaho Chemical Processing Plant (ICPP), WINCO Environmental Engineering Section, 1988, 62 p.
- DeVoe Paint Manufacturing, Salt Lake City, UT. Telecommunications, 1990.
- Doherty, D. J., McBroome, L. A., and Kuntz, M. A., Preliminary Geological Interpretation and Lithologic Log of the Exploratory Geothermal Test Well (INEL-1), Idaho National Engineering Laboratory, Eastern Snake River Plain, Idaho, OP 79-1248, U.S. Geological Survey, Idaho Falls, Idaho, 1979.
- Environmental Protection Agency (1987), Test Methods for Evaluating Solid Waste (SW-846), 3rd edition, Waste Management Division, Office of Solid Waste, US Environmental Protection Agency, Washington D.C.
- Environmental Protection Agency (1988a), Laboratory Data Validation Functional Guidelines for Evaluating Inorganic Analyses, Hazardous Site Evaluation Division, US Environmental Protection Agency, Washington D.C.
- Environmental Protection Agency (1988b), Laboratory Data Validation Functional Guidelines for Evaluating Organic Analyses, Hazardous Site Evaluation Division, US Environmental Protection Agency, Washington D.C.
- Environmental Protection Agency (1989a), RCRA Facility Investigation (RFI) Guidance, Volume I: Interim Final, EPA/530/SW-89-031, OWSER Directive 9503.00-6D, Office of Solid Waste, US Environmental Protection Agency, Washington D.C.
- Environmental Protection Agency (1989b), Health Effects Assessment Summary Tables - Fourth Quarter FY-89, OWSER (OS-230) ORD (RD-689), OERR 9200.6-303-(89-4), Environmental Criteria and Assessment Office, US Environmental Protection Agency, Washington D.C.
- Golder Associates (1990a), Technical Work Plan for the Idaho Chemical Processing Plant Drilling and Sampling Program at Land Disposal Units CPP-34, and CPP-55 (volumes I and II), Golder Associates Inc., Redmond WA.
- Golder Associates (1990b), Report for the Idaho Chemical Processing Plant Drilling and Sampling Program at Land Disposal Unit CPP-55, Golder Associates Inc., Redmond WA.
- Golder Associates (1990c), Quality Assurance Program Plan: INEL/ICPP Land Disposal Unit Characterization Support, Golder Associates Inc., Redmond WA.
- Mann, Larry J., Hydraulic Properties of Rock Units and Chemical Quality of Water for INEL-1 - A 10,365 foot Deep Test Hole Drilled at the Idaho National Engineering Laboratory, Idaho, IDO-22070, U.S. Geological Survey, Idaho Falls, Idaho, 1986.

University of Utah Research Institute (1986), FPR Warehouse Site, Idaho Chemical Processing Plant, University of Utah Research Institute, Salt Lake City UT.

University of Utah Research Institute (1987), Chemical Storage and Zirconium Feed Tank Storage Areas, University of Utah Research Institute, Salt Lake City UT.

Westinghouse Idaho Nuclear Corporation, Inc. (WINCO) (January, 1989), Closure Plan For CPP-55, Mercury Contaminated Area (South of ICPP T-15), WINCO, Idaho Falls, ID.

**APPENDIX A**  
**HEALTH AND ENVIRONMENTAL ASSESSMENT**

## HEALTH AND ENVIRONMENTAL ASSESSMENT

A Health and Environmental Assessment (HEA) is conducted to evaluate the potential harmful impacts of hazardous constituents present at a site. The HEA involves identifying the contaminants of concern, the concentrations of those contaminants in the affected environmental media, and the exposed, or potentially exposed, human and environmental receptors. The essential element of any HEA is the development of appropriate health and environmental criteria, to which the measured toxin concentrations can be compared. These criteria are based primarily on EPA-established chronic exposure limits. When one or more of these criteria are exceeded, there is the likelihood for adverse health or environmental effects.

The following HEA evaluates the potential impacts associated with the contaminants detected in the sampling program for LDU CPP-55.

### A.1 IDENTIFICATION OF TOXIC CONTAMINANTS

Analyses for the presence and concentration of ten metals were conducted on the shallow soil samples from LDU CPP-55. Of the ten metals analyzed, five were either not detected or are essential elements for human health at the concentrations of concern. Silver was not evaluated because of its low, uniform distribution. The remaining four metals, arsenic, chromium, lead, and mercury, were assessed for health and environmental impacts.

Arsenic is a suspected human carcinogen by inhalation and is a confirmed skin carcinogen via ingestion. Arsenic may occur in either of two valence states, the trivalent (+3) and the pentavalent (+5). The trivalent form is more toxic than the pentavalent form; and the inorganic form is more toxic than the organic form.

Chromium exists in one of three valence states (+2, +3, +6). Adverse health affects are associated with the hexavalent form. This form is associated with

lung and respiratory tract cancer resultant from inhalation. There is no evidence of carcinogenicity from ingestion of hexavalent chromium.

Lead is a well documented cumulative toxin, associated within laboratory animals. Because of the extremely low blood lead levels at which adverse effects can occur, the EPA has recommended that neither a chronic reference dose nor a numerical cancer risk estimate be used.

Mercury toxicity is highly dependent on the form, organic or inorganic, and the route of exposure, inhalation or ingestion. Target organs for toxic effects are the central nervous system and kidneys. Mercury has not been classified as a human carcinogen.

Of the three organic compounds detected, toluene, bis (2-ethylhexyl) phthalate (BEHP), and 4-methyl 2-pentanone, none were found at levels that would pose a health or environmental hazard. Conservative screening calculations of BEHP, a possible human carcinogen, is  $1E-08$ . Thus no organic compounds were evaluated in this HEA.

## A.2 IDENTIFICATION OF EXPOSURE PATHWAYS

The contamination detected at CPP-55 has been localized in the soil. Migration and transportation of these metals to other media could influence potential exposure pathways. However, due to the extreme depth to groundwater, the lack of any nearby surface water bodies, and the extremely low vapor pressures of these compounds, the main routes for exposure are through ingestion and dermal contact with contaminated soil. Because of the chemical forms of these metals in soils, the primary concern is through ingestion.

## A.3 IDENTIFICATION OF RECEPTOR POPULATIONS

The identification of a receptor population for exposure at LDU CPP-55 is very straightforward. This unit is located inside of a secured area with limited access. Therefore, a reasonable assumption is that an adult worker represents

the typical receptor (industrial scenario). For comparison purposes, and to evaluate the carcinogenic risk for arsenic, an adult residential scenario was also calculated.

#### A.4 HUMAN HEALTH ASSESSMENT

Screening criteria and calculated intakes for the identified metals, using soil ingestion as the exposure route and an adult worker as the receptor, were used to assess the human health effects at LDU CPP-55. Table A.1 summarizes the results of this assessment.

General assumptions used in this calculation include:

- Maximum concentrations of detected metals were used;
- toxicity is limited to chronic toxicity or carcinogenicity;
- chemical intakes were calculated using the EPA standard intake equation (EPA 1989c);
- upper bound exposure parameters, as recommended by USEPA Region X, were used in all intake calculations (EPA, 1990b).

Several criteria were used to evaluate the potential health effects of the metals detected at LDU CPP-55. First was the calculation of a maximum allowable soil concentration based on system toxicity and using a sensitive population (16kg child, ingesting 200 mg of soil per day over a 5 year period). This screening criteria was conducted as recommended in the RCRA Facility Investigation Guidance (EPA, 1989c). Soil concentrations for arsenic, chromium, and mercury did not exceed the calculated maximum. The calculation for lead was not conducted because its concentration (32 mg/kg) was below that necessary to produce an increase in blood lead levels in children (>500 mg/kg).

Secondly, when chronic intakes from exposure for both scenarios were compared to background levels only chromium and mercury exceeded the chronic intake health risk that might occur with exposure to background levels of these metals.



Constituent	Background Soil Concentration (mg/kg)	Maximum Detected Soil Concentration		Screening Criteria			Chemical Intake and Hazard Quotients				Other Information
				Chronic Oral/RfD (mg/kg/day)	Chronic Intake from Background (mg/kg/day)	Maximum Soil Concentration for Sensitive Population (mg/kg)	Industrial Scenario		Residential Adult Scenario		
		Chemical Intake (mg/kg/day)	Hazard Quotient				Chemical Intake (mg/kg/day)	Hazard Quotient			
Arsenic	8.7	8.0	13.4	1E-3 <sup>a</sup>	1.7E-6	80 <sup>d</sup>	3.6E-6	0.0036	2.7E-6	0.0027	Cancer Risk Associated with Oral Arsenic Intakes: Background : 2.9E-6 Industrial : 6.1E-6 Residential : 4.6E-6
Chromium	42	40.5	64.7	5E-3 <sup>b</sup>	8.4E-6	400 <sup>d</sup>	1.8E-5	0.0036	1.3E-5	0.0026	There is no evidence that chromium (VI) is carcinogenic by the oral route
Lead	21	28.7	32	ND <sup>a</sup>	4.2E-6	500 <sup>e</sup>	8.6E-6	—	6.4E-6	—	Quantitative evaluation not recommended because toxic effects may be without a threshold
Mercury (Inorganic)	0.07	5.2	5.2	3E-4 <sup>a</sup>	1.4E-8	24 <sup>d</sup>	1.4E-6	0.0047	1.0E-6	0.0033	RfD based on adverse central nervous system effects

a Source: Health Assessment Summary Tables, Fourth Quarter, 1989.

b Source: Integrated Risk Information System (IRIS) Access Date 4/4/90.

c Not Determined.

d Calculated Soil Concentrations.

e Soil Lead Concentrations > 500mg/kg May Produce Increase Blood Lead Levels in Children

Table A.1

SUMMARY OF HEA FOR LDU CPP-55

EG&G/ICPP/10

The final criteria compared the calculated chemical intake with the chronic oral reference dose published in either the Integrated Risk Information Service or the Health Assessment Effects Summary Tables. The chronic oral reference dose (RfD) is defined as the dose to which an individual might be exposed on a daily basis for a lifetime without developing documented critical toxic effects. None of the chronic chemical intakes for any of the constituents found at LDU CPP-55, for either residential or industrial scenarios, were above their respective RfDs.

To further characterize the potential non-cancer health effects from exposure the hazard quotient (ratio of chemical intake to RfD) was calculated. The non-cancer hazard quotient assumes that there is a level of exposure below which even very sensitive populations may experience no adverse health effects. If this ratio exceeds 1.0, then there may be concern for potential non-carcinogenic health effects. All hazard quotients, for the three metals evaluated (lead does not have an RfD), were significantly below 1.0 (see Table A.1). The combined hazard quotient for the effects of all three metals was also significantly below 1.0 (0.0119 for the industrial scenario and 0.0086 for the residential scenario).

Because of the documented carcinogenicity associated with the oral exposure route to arsenic a cancer risk for this unit was calculated. The risk for all exposure scenarios was found to be at the  $1 \times 10^{-6}$  level (see Table A.1).

#### A.5 ENVIRONMENTAL ASSESSMENT

Arsenic, chromium, and lead exhibit low potential toxicity for plants and somewhat higher toxicity for animals. Mercury will readily translocate in plants and may undergo biomagnification in the food chain, and is particularly toxic to aquatic animals. However, the potential for environmental effects from the contamination at the site is minimal. LDU CPP-55 is located within a fenced industrial area. Vegetation within the ICPP is controlled with herbicides, while large animals are restricted from the area by animal control fences.

**APPENDIX B**  
**BOREHOLE LOGS**




PROJECT: WINCO/CPP/ID  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195.020

# RECORD OF BOREHOLE CPP-55-2

BORING DATE: 4 JANUARY 1990  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1  
 DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	WATER CONTENT, PERCENT				
					DEPTH						Wp ——— W				
0	4 INCH HOLLOW STEM AUGER (ISA)	Dense (frozen), dark yellowish brown (10YR4/2), unstratified, damp, GRAVEL and SAND, trace silt, (GW-SW) (FILL)	GW-SW		0.00										
1					1	G	N/A		2.0/2.0						
2		Dense (frozen), dark yellowish brown (10YR4/2), unstratified, damp, SAND and GRAVEL, trace silt, (GW-SW) (FILL or ALLUVIUM)	GW-SW		2.00										
3					2	G	N/A		2.0/2.0						
4		Very dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND and GRAVEL, little silt, (SW-GW) (FILL or ALLUVIUM)	SW-GW		4.00										
5					3	HD	23.92.90	182	1.5/2.0						
6		6.0 FT TOTAL DEPTH OF BOREHOLE Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.			6.00										
7															
8															

WELL RIG: CME-55  
 DRILLING CONTRACTOR: Hawley Brothers  
 DRILLER: Dan Hawley

Golder Associates

LOGGED: S Brandenberger  
 CHECKED: R. Burk  
 DATE: 19 JANUARY 1990

PROJECT: WINCO/ICPP/ID  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195.020

# RECORD OF BOREHOLE CPP-55-1

BORING DATE: 19 DECEMBER 90  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1  
 DATUM: MSL



DEPTH FEET	BORING METHOD	SOIL PROFILE				SAMPLES				PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	USCS	GRAPHIC LOG ELEV DEPTH	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	20	40	60	80	
0	4 INCH FLOW STEM AUGER (HSA)	Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, damp, SAND and fine GRAVEL, some Silt, (SM-GM) (FILL) 0.0-0.5 ft. clay layer 1.0-1.1 ft. clay layer	SM-GM	0.00	1	HD	242,427,341,271	812	2.0/2.0					
2		Very dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND and fine GRAVEL, little silt, (SW-GP) (FILL or ALLUVIUM)	SW-GP	2.00	2	HD	26,30,29,33	82	1.6/2.0					
4		Very dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND and GRAVEL, trace silt, (SW-GW) (FILL or ALLUVIUM)	SW-GW	4.00	3	HD	21,26,27,30	57	1.6/2.0					
6		6.0 FT TOTAL DEPTH OF BOREHOLE  Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.		6.00										

DRAWN BY CME-SS  
 DRILLING CONTRACTOR: Hawley Brothers  
 DRILLER: Dan Hawley

Golder Associates

LOGGED: T. Griffin  
 CHECKED: R. Burn  
 DATE: 19 DECEMBER 90



PROJECT: WINCO/ICPP/ID  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195

# RECORD OF BOREHOLE CPP-55-2A

BORING DATE: 4 January 90  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1  
 DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV DEPTH	NUMBER	TYPE	BLOWS / 6 in	X	REC/ATT	WATER CONTENT, PERCENT				
											Wp	Wc	W		W
0	4 INCH HOLLOW STEM AUGER (HSA)	Dense (frozen), dark yellowish brown (10YR4/2), unstratified, damp, GRAVEL and SAND, trace Silt (SW-GW) (FILL)	SW-G		0.00										
1					1	G	N/A		2.0/2.0						
2		Dense, Dark yellowish brown (10YR4/2), unstratified, damp, GRAVEL and SAND, trace Silt (SW-GW) (FILL)	SW-G		2.00	2	HD	50+		0.0/0.7					
3		2.7 FT TOTAL DEPTH OF BOREHOLE			2.70										
4		Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.													
5		Refer to Record of Borehole CPP-55-2													
6															
7															
8															

DRILL RIG CME-55  
 DRILLING CONTRACTOR Hawley Brothers  
 DRILLER Dan Hawley

Golder Associates

LOGGED: S Brandenberger  
 CHECKED: R Burt  
 DATE: 4 January 90

PROJECT: WINCO/ICPP/D  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195.020

# RECORD OF BOREHOLE CPP-55-3

BORING DATE: 19 JANUARY 1990  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1  
 DATUM: MSL



DEPTH SCALE (FEET)	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	20 40 60 80				
					DEPTH						WATER CONTENT, PERCENT				
											WP	—	W		
0	4 INCH HOLLOW STEM AUGER (ISA)	Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, dry, SAND and fine GRAVEL, little silt and clay, (SW-GW) (FILL)  (140 lb hammer used for Sample 1)	SW-G		0.00	1	HD	543,385,1'		0.7/0.7					
1		Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, dry, SAND and GRAVEL (SW-GW) (FILL)	GW-S		0.70	2	G	N/A		4/1.4					
2															
3		Dense, dark yellowish brown (10YR4/2), unstratified, dry, SAND and GRAVEL, little silt, (SW-GW) (FILL or ALLUVIUM)	SW-G		2.10	3	HD	30,21,17,14	31	8/2.0	■				
4															
5		Compact, dark yellowish brown (10YR4/2), unstratified, dry, GRAVEL, some SAND, trace silt, (SW-GW) (ALLUVIUM or FILL)	SW-G		4.10	4	HD	7,8,13,14	27	8/2.0	■				
6															
7		6.1 FT TOTAL DEPTH OF BOREHOLE			8.10										
8		*Note: Unless specified, HD refers to a 4.0 inch OD split spoon advanced with a 300 lb. hammer with a 30 inch drop.													

DRILL R/G: CME-55  
 DRILLING CONTRACTOR: Hawley Brothers  
 MILLER: Dan Hawley

Golder Associates

LOGGED: J. Wozniak  
 CHECKED: R. Burk  
 DATE: 19 JANUARY 1990




PROJECT: WINCO/ICPP/10  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195.020

# RECORD OF BOREHOLE CPP-55-4

BORING DATE: 4 JANUARY 1990  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1  
 DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE				PIEZOMETER OR STANDPIPE INSTALLATION		
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	BLOWS/FT ■					
					DEPTH						20	40	60		80	
												WATER CONTENT, PERCENT				
												Wp ———— W				
0	4 INCH FLOW STEM ALKOR (ISA)	Dense to very dense (frozen), dark yellowish brown (10YR4/2), unstratified, damp, SAND and GRAVEL (GW-SW) (FILL)			0.00											
1			GW-SW			1	G	N/A		2.0/2.0						
2																
3			Very dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND and fine GRAVEL, trace silt and clay, (GW-SW) (FILL or ALLUVIUM)			2.00										
4			GW-SW			2	HD	106, 109, 65, 37	102	3.2/0						
5																
6		Very dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND and fine GRAVEL, trace silt and clay, (SW-GW) (FILL or ALLUVIUM)			4.00											
7			SW-GW			3	HD	15, 23, 36, 38	74	5.2/0						
8																
9		6.0 FT TOTAL DEPTH OF BOREHOLE			6.00											
10		Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.														

DRILL RIG: CME-55  
 DRILLING CONTRACTOR: Hawley Brothers  
 DRILLER: Dan Hawley

Golder Associates

LOGGED: T. Griffin  
 CHECKED: R. Burk  
 DATE: 4 JANUARY 1990



PROJECT: WINCO/ICPP/ID

PROJECT LOCATION: INEL

PROJECT NUMBER: 893-1195.020

## RECORD OF BOREHOLE CPP-55-5




BORING DATE: 20 DECEMBER 90

BORING LOCATION: ICPP-55

SHEET: 1 OF 1

DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	WATER CONTENT, PERCENT				
					DEPTH						Wp	Cw	Wl		
0	4 INCH HOLLOW STEM AUGER (HSA)	Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, dry, SAND and fine GRAVEL (SW-GW) (FILL)	SW-GP		0.00										
1					1	HD	24,166,258,233	491	0.3/2.0						
2		Dense, dark yellowish brown (10YR4/2), unstratified, dry, medium to coarse SAND and GRAVEL (SW-GP) (ALLUVIUM or FILL)	SW-GP		2.00										
3					2	HD	14,15,14,17	31	2.0/2.0						
4		Very dense, dark yellowish brown (10YR4/2), unstratified, dry, medium to coarse SAND and fine GRAVEL (SW-GW) (ALLUVIUM or FILL)  (140 lb hammer used for Sample 3)	SW-GP		4.00										
5	3				HD	10,16,20,36	56	0/2.0							
6		6.0 FT TOTAL DEPTH OF BOREHOLE													
7		*Note: Unless specified, HD refers to a 4.0 inch OD split spoon advanced with a 300 lb. hammer with a 30 inch drop.													
8															

LOG RIG CME-55  
 DRILLING CONTRACTOR: Hawley Brothers  
 DRILLER: Dan Hawley

Golder Associates

LOGGED: J. Wozniak  
 CHECKED: R. Burk  
 DATE: 20 DECEMBER 90


PROJECT: WINCO/ICPP/ID  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195

# RECORD OF BOREHOLE CPP-55-5A

BORING DATE: 21 December 89  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1  
 DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	RECIPT	WATER CONTENT, PERCENT				
					DEPTH						w <sub>p</sub> ——— w ——— w <sub>L</sub>				
0	4 INCH HOLLOW STEM AUGER (HSA)	Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, SAND and GRAVEL, some Silt, (SW-GW) (FILL)	SW-GW		0.00	1	G	N/A		2.0/2.0					
1															
2		2.0 FT TOTAL DEPTH OF BOREHOLE				2.00									
3		Refer to Record of Borehole CPP-55-5													
4															
5															
6															
7															
8															

DRILL RIG CME-55  
 DRILLING CONTRACTOR: Hawley Brothers  
 DRILLER: Dan Hawley

Golder Associates

LOGGED: J. Wozniak  
 CHECKED: R. Burk  
 DATE: 21 December 89




PROJECT: WINCO/ICPP/D  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195.020

# RECORD OF BOREHOLE CPP-55-6

BORING DATE: 6 February 1990  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 9  
 DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT				PIEZOMETER OR STANDPIPE INSTALLATION					
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV DEPTH	NUMBER	TYPE	BLOWS / 8 in	N	REC/ATT	WATER CONTENT, PERCENT								
											Wp	OW	W						
0	4 INCH TITLOW STEM AUGER (USA)	Dense to very dense, dark yellowish brown (10YR4/2), unstratified, SAND and GRAVEL, trace silt, damp, (SW-GW) (FILL?)	SW-GW		0.00														
1					1	G	N/A		2.0/2.0										
2					2A	HD	80/3		3/3										
							Augered												
3					2B	HD	10/2,45,60	105	1.0/1.2										
4																			
5		3	HD	40,58,30,60	90	2.0/2.0													
6		5.8-6.0 ft. Firm, dark yellowish brown (10YR4/2), stratified, SILT, some sand and gravel, damp, (SM-GW) (ALLUVIUM)	SM-GW		5.80 6.00														
7		Dense to very dense, dark yellowish brown (10YR4/2), unstratified, SAND and GRAVEL, trace silt, damp, (SW-GW) (ALLUVIUM)	SW-GW																
7					4	HD	18,27,20	47	1.5/1.5										
8																			
9					5	HD	16,23,24,30	54	2.0/2.0										
10																			
11					6	HD	16,30,35,45	80	2.0/2.0										
12					7A	HD	108/6												
13	7B	HD																	
14																			
15																			
16																			

DRILLING CONTRACTOR: CME-55  
 DRILLING CONTRACTOR: Hawley Brothers  
 DRILLER: Dan Hawley

Golder Associates

LOGGED: J. Wozniak  
 CHECKED: R. Burt  
 DATE: 6 February 1990

PROJECT: WINCON/CPP/10

PROJECT LOCATION: INEL

PROJECT NUMBER: 893-1195.020

## RECORD OF BOREHOLE CPP-55-6

BORING DATE: 6 February 1990

BORING LOCATION: ICPP-55

SHEET: 2 OF 9

DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES						PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION				
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV DEPTH	NUMBER	TYPE	BLOWS / 8 in	N	REC/ATT	WATER CONTENT, PERCENT								
											Wp	W	Wp	W					
16	4 INCH HOLLOW STEM AUGER (HSA)	Compact to very dense, dark yellowish brown (10YR4/2), unstratified, SAND and GRAVEL, trace silt, damp, (SW-GW) (ALLUVIUM)  20.0 ft: wet soil at bottom of sample 10.	SW-GW				Augered												
17					9	HD	48,78,85	163	5/1.5										
18																			
19					10	HD	45,78,91,92	183											
20																			
21					11	HD	64,115	179	0.8/1.4										
22							Augered												
23					12	HD	30,42,30,33	83	4/2.0										
24																			
25					13	HD	18,45,58,63	121	9/2.0										
26																			
27					14	HD	58,120		1.0/1.0										
28							Augered												
29					15	HD	25,77,84,10	94	2.0/2.0										
30																			
31					16	HD	48,88,38,66	106	2.0/2.0										
32																			

DRILL RIG: CME-55

DRILLING CONTRACTOR: Hawley Brothers

DRILLER: Dan Hawley

Golder Associates

LOGGED: J. Wozniak

CHECKED: R. Burk

DATE: 6 February 1990

PROJECT: WINCO/ICPP/10

## RECORD OF BOREHOLE CPP-55-6

SHEET: 3 OF 9

PROJECT LOCATION: INEL

BORING DATE: 6 February 1990

DATUM: MSL

PROJECT NUMBER: 893-1195.020

BORING LOCATION: ICPP-55



ELEVATION (FEET)	BORING MEASUREMENT	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	REG/ATT	BLOWS/FT ■				
					DEPTH						20	40	60		80
											WATER CONTENT, PERCENT				
											Wp	W			
32	4 INCH HOLLOW STEM AUGER (ISA)	Compact to very dense, dark yellowish brown (10YR4/2), unstratified, SAND and GRAVEL trace silt, damp, (SW-GW) (ALLUVIUM)	SW-GW		32.00			Augered							
33															
34															
35															
36															
37															
38															
39															
40															
41															
42		Firm to soft, dark yellowish brown (10YR4/2) to grayish orange (10YR7/4), stratified, silt to clayey silt, trace to some sand, slightly damp, (CL-ML)	CL-ML		40.30										
43															
44															
45		43.7 FT. ALLUVIUM/BASALT CONTACT			43.70										
46															
47		Note: HD refers to 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.													
48															

CPL RG CME-55

DRILLING CONTRACTOR: Hawley Brothers

DRILLER: Dan Hawley

LOGGED: J. Wozniak

CHECKED: R. Burk

DATE: 6 February 1990

Golder Associates

## Sheet 4 of 9

COLLAR ELEV:  
E:  
INCLINATION:

 **Golder Associates**

# RECORD OF DRILLHOLE CPP-55-6

Sheet 5 of 9

PROJECT: WINCONEL/10  
PROJECT NO: 883-1195.020  
LOCATION: INEL

DRILLING DATE: 2/19-2/22, 1990  
DRILL RIG: CME 55

DATUM: MSL  
COORDINATES N:  
AZIMUTH:

COLLAR ELEV:  
E:  
INCINATION: 90

ROCK TYPE		DISCONTINUITY DATA										HYDRAULIC CONDUCTIVITY cm/sec	NOTES WATER LEVELS INSTRUMENTATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
DESCRIPTION	GRAPHIC LOG	J-Joint F-Fault S-Shear B-Bedding F-Foliation		PL-Planar C-Curved U-Undulating ST-Stepped I-Irregular		P-Polished K-Silver-sanded SM-Smooth R-Rough VR-V. Rough		FR-Fracture CL-Clay Coating SP-Sub-planar IN-Clay infilling		TYPE AND SURFACE DESCRIPTION	GRAPHIC LOG																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
		ELEV DEPTH (FT)	RUN NO.	CORE RECOVERY	RQD	2 3 4 5 6 7 8 9 10	11 12 13 14 15 16 17 18 19 20	21 22 23 24 25 26 27 28 29 30	31 32 33 34 35 36 37 38 39 40																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
48 Fresh, medium dark gray (N4) to dark gray (N3), moderately vesicular, aphanitic, medium strong, BASALT			1	100																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											</

DEPTH SCALE: 1 INCH=2 FEET  
DRILLING CONTRACTOR: HAWLEY BROTHERS  
CALLER: J. HAWLEY

LOGGED: J. WOZNIEWCZ/T. GRIFFIN  
CHECKED: R. Burt  
DATE: 19 FEBRUARY 1990

 Golder Associates

# RECORD OF DRILLHOLE CPP-55-6

Sheet 6 of 9

PROJECT: WINCO/INEL10  
PROJECT NO: 883-1185.020  
LOCATION: INEL

DRILLING DATE: 2/18-2/22, 1990  
DRILL RIG: CME 33

DATUM: MSL  
COORDINATES N:  
AZMUTH:

COLLAR ELEV:  
E:  
INCLINATION: 80

DEPTH SCALE (FEET)	ROCK TYPE		GRAPHIC LOG	J-Joint F-Fault S-Shear B-Bedding F-Foliation				PL-Planar C-Curved U-Undulating ST-Stepped I-Irregular				P-Polished K-Skinned SM-Smooth R-Rough VRL-V. Rough				FR-Fracture CL-Clay Coating SP-Sub-surface IN-Clay Infilling				HYDRAULIC CONDUCTIVITY cm/sec	NOTES WATER LEVELS INSTRUMENTATION	
	DESCRIPTION	ELEV DEPTH (FT)		RUN NO.	CORE RECOVERY	RQD	FRACTURES PER FOOT	DISCONTINUITY DATA				TYPE AND SURFACE DESCRIPTION	GRAPHIC LOG									
								DIP	Wrt CORE AXIS	00	00											
64	Fresh, slightly vesicular, dark gray (N3), aphanitic, medium strong, BASALT																					
65																						
66				5	100																	
67																						
68																						
69	Fresh, vesicular, brownish gray (SYR2/1), aphanitic, medium strong, BASALT	68.90																				
70																						
71				6	88																	
72																						
73																						
74																						
75	Slightly weathered, vesicular, moderate orange pink (10YR7/4) to pale red (SYR6/2), aphanitic, weak to medium strong, rubbly BASALT	74.10		7	0																	
76	Fresh, massive, vesicular, grayish red (5R4/2) to dusky brown (SYR2/2) at bottom of run 8, aphanitic, BASALT	75.60																				
77				8	85																	
78																						
79		78.00		9	80																	
80																						

DEPTH SCALE: 1 INCH=2 FEET  
DRILLING CONTRACTOR: HAWLEY BROTHERS  
DRILLER: D. HAWLEY

LOGGED: J. WOZNIEWICZ/T. GRIFFIN  
CHECKED: R. Burk  
DATE: 18 FEBRUARY 1990

 Golder Associates



# RECORD OF DRILLHOLE CPP-55-6

Sheet 7 of 9

PROJECT: WINCO/NEL/D  
PROJECT NO: 883-1195.020  
LOCATION: INEL

DRILLING DATE: 2/19-2/22, 1990  
DRILL RIG: CME 55

DATUM: MSL  
COORDINATES N:  
AZIMUTH:

COLLAR ELEV:  
E:  
INCLINATION: 90

DEPTH SCALE (FEET)	ROCK TYPE	DESCRIPTION	GRAPHIC LOG	DISCONTINUITY DATA										HYDRAULIC CONDUCTIVITY cm/sec	NOTES WATER LEVELS INSTRUMENTATION
				J-Joint F-Fault S-Shear B-Bedding F-Foliation		PL-Planar C-Curved U-Undulating ST-Stepped H-Irregular		P-Polished K-Skimmed SM-Smooth R-Rough VH-V. Rough		FR-Fracture CL-Clay Coating SP-Sub-planar IN-Clay Infilling		GRAPHIC LOG			
				ELEV DEPTH (FT)	RUN NO.	CORE RECOVERY	RCO	2 FRACTURES PER FOOT	30 DP Wt CORE AXIS	60 AXIS	80				
80		Fresh, massive, vesicular, dusky brown (5YR2/2), aphanitic, BASALT													
81															
82				9	80							J,SP,R			
83												J,P,R			
84												J,SP,R,IN			
85		Fresh, slightly vesicular, medium dark gray (N4), aphanitic, medium strong, BASALT		84.00								J,SP,R			Radiation level 1000 counts/min at 83 ft.*
86												J,SP,R,IN			
87				10	100							J,P,SM,IN			
88												J,SP,R,IN			
89												J,P,SM,IN			
90												J,SP,SM			
91												J,PL,U,SM,IN			
92												J,C,SM,IN			
93												J,I			
94				11	97							J,PL,SM,IN			
95												J,SP,SM,IN			
96															
97															
98															
99															
100															
101															
102															
103															
104															
105															
106															
107															
108															
109															
110															
111															
112															
113															
114															
115															
116															
117															
118															
119															
120															
121															
122															
123															
124															
125															
126															
127															
128															
129															
130															
131															
132															
133															
134															
135															
136															
137															
138															
139															
140															
141															
142															
143															
144															
145															
146															
147															
148															
149															
150															
151															
152															
153															
154															
155															
156															
157															
158															
159															
160															
161															
162															
163															
164															
165															
166															
167															
168															
169															
170															
171															
172															
173															
174															
175															
176															
177															
178															
179															
180															
181															
182															
183															
184															
185															
186															
187															
188															
189															
190															
191															
192															
193															
194															
195															
196															
197															
198															
199															
200															

DEPTH SCALE: 1 INCH=2 FEET  
DRILLING CONTRACTOR: HAWLEY BROTHERS  
DRILLER: C HAWLEY

LOGGED: J. WOZNIEWICZ/T. GRIFFIN  
CHECKED: P. BURN  
DATE: 19 FEBRUARY 1990

 Golder Associates

# RECORD OF DRILLHOLE CPP-55-6

Sheet 8 of 9

PROJECT: WINCO/INEL/0  
PROJECT NO: 883-1185.020  
LOCATION: INEL

DRILLING DATE: 2/19-2/22, 1990  
DRILL RIG: CME 55

DATUM: MSL  
COORDINATES N:  
AZIMUTH:

COLLAR ELEV:  
E:  
INCLINATION: 90

DEPTH SCALE (FEET)	ROCK TYPE	DESCRIPTION	GRAPHIC LOG	DISCONTINUITY DATA										HYDRAULIC CONDUCTIVITY cm/sec	NOTES WATER LEVELS INSTRUMENTATION
	J-Joint F-Fault S-Shear B-Bedding F-Foliation			PL-Planar C-Curved U-Unconformity ST-Stepped I-Irregular		P-Polished K-Skimmed SM-Smooth R-Rough VR-V. Rough		FR-Fracture CL-Clay Coating SP-Sub-granular IN-Clay Infilling							
	ELEV DEPTH (FT)			RUN NO.	CORE RECOVERY	R.O.C.	2 3 4 5 6 7 8 9 10	DISCONTINUITY DATA	TYPE AND SURFACE DESCRIPTION	GRAPHIC LOG					

96	Fresh, slightly vesicular, medium dark gray (N4), aphanitic, medium strong, BASALT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
----	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

DEPTH SCALE 1 INCH=2 FEET  
DRILLING CONTRACTOR: HAWLEY BROTHERS  
DRILLER: D. HAWLEY

LOGGED: J. WOZNIEWICZ/T. GRIFFIN  
CHECKED: R. Burk  
DATE: 19 FEBRUARY 1990

 Golder Associates

# RECORD OF DRILLHOLE CPP-55-6

Sheet 9 of 9

PROJECT: WINCO/INEL/10  
PROJECT NO: 893-1195.020  
LOCATION: INEL

DRILLING DATE: 2/19-2/22, 1990  
DRILL RIG: CME 55

DATUM: MSL  
COORDINATES N:  
AZIMUTH:

COLLAR ELEV:  
E:  
INCLINATION: 90


DEPTH SCALE (FEET)		ROCK TYPE		DESCRIPTION	GRAPHIC LOG	ROCK TYPE										HYDRAULIC CONDUCTIVITY cm/sec	NOTES WATER LEVELS INSTRUMENTATION
		J-Joint F-Fault S-Shear B-Banding P-Polished				PL-Planar C-Curved U-Unconformity ST-Stepped I-Irregular		P-Polished K-Silicified SM-Smooth RL-Rough VR-V. Rough		FR-Fracture CL-Clay Coating SP-Sub-planar IN-Clay infilling		DISCONTINUITY DATA					
		ELEV DEPTH (FT)	RUN NO.			CORE RECOVERY	LOG	FRACTURES PER FOOT	DIP W/1 CORE 80 AXIS	TYPE AND SURFACE DESCRIPTION	GRAPHIC LOG						
112																	
113																	
114			16	100						J, PL-U, SM, IN					Radiation level 4500 counts/min at 114 ft. *		
115																	
116			17	100													
117																	
118																	
119			18	100						J, SP, SM, IN J, SP, R, IN J, I, SM-R, IN							
120																	
121															*Note: All Radiation monitoring conducted by WINCO.		
122																	
123															** Radiation survey performed through lexan tube.		
124																	
125																	
126																	
127																	
128																	

DEPTH SCALE: 1 INCH = 2 FEET  
DRILLING CONTRACTOR: HAWLEY BROTHERS  
DRILLER: D. HAWLEY

LOGGED: J. WOZNIEWICZ/T. GRIFFIN  
CHECKED: R. Burk  
DATE: 19 FEBRUARY 1990

 Golder Associates

# STRATIGRAPHY



## WELL COMPLETION LEGEND:

- |                      |                                |
|----------------------|--------------------------------|
| Cement Grout         | 2" Stainless Steel Well Casing |
| 3-5% Bentonite       | 2" S.S. Well Screen 0.020-slot |
| 1/4" Velscoy Tablets |                                |
| 10-20 Silica Sand    |                                |
| Water Level          |                                |

NOT TO SCALE

Date: 4/23/90  
Geologist: SJB  
Drilling Contractor: HAWLEY BROS.  
Drill Method: CP CORE  
Sampling Method: -

FIGURE 1  
SHEET 1 OF 1  
WELL **CPP55-06**  
RECORD OF  
DRILLHOLE  
INEL

PROJECT: WINCO/ICPP/D  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195.020

# RECORD OF BOREHOLE CPP-55-7

BORING DATE: 21 DECEMBER 90  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1  
 DATUM: MSL



DEPTH (SCALE FEET)	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	REG/ATT	BLOWS/FT ■				
					DEPTH						20	40	60		80
											WATER CONTENT, PERCENT				
											Wp	W			
0	4 INCH HOLLOW STEM AUGER (ISA)	Very dense (frozen), moderate brown (5YR4/4), unstratified, dry, SAND and GRAVEL, some SILT, (SW-GW) (ALLUVIUM or FILL)	SW-G		0.00										
1					1	G	N/A	2.0/2.0							
2															
3					Very dense, dark yellowish brown (10YR4/2) to moderate brown(5YR4/4), unstratified, dry, medium to coarse SAND and GRAVEL, little silt, (SW-GW) (ALLUVIUM or FILL)	SW-G	2	HD	36,57,55,47	102	.8/2.0				
4		Very dense, moderate brown (5YR3/4), unstratified, dry, medium to coarse SAND and GRAVEL, trace silt, (SW-GW) (ALLUVIUM or FILL)	SW-G		4.00										
5					3	HD	21,32,27,32	58	.0/2.0						
6															
7		6.0 FT TOTAL DEPTH OF BOREHOLE					6.00								
8		Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.													

DRILL RIG: CME-55  
 DRILLING CONTRACTOR: Hawley Brothers  
 DRIVER: Dan Hawley

Golder Associates

LOGGED: J. Wachniewcz  
 CHECKED: R. Burk  
 DATE: 20 DECEMBER 90

PROJECT: WINCO/ICPP/D

## RECORD OF BOREHOLE CPP-55-8

SHEET: 1 OF 1

PROJECT LOCATION: INEL





BORING DATE: 3 JANUARY 1990

DATUM: MSL

PROJECT NUMBER: 883-1195.020

BORING LOCATION: ICPP-55



DEPTH SCALE (FEET)	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 8 in	N	RECIPT	20 40 60 80				
					DEPTH						WATER CONTENT, PERCENT Wp ——— W ——— W				
0	4 INCH HOLLOW STEM AUGER (ISA)	Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, GRAVEL, some SAND, trace silt (SW-GW) (FILL)	SW-GW		6.00										
1		Dense, dark yellowish brown (10YR4/2), unstratified, damp, GRAVEL and SAND, trace silt (SW-GW) (ALLUVIUM or FILL)	SW-GW		1.00	1	G	N/A		2.0/2.0					
2		Very dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND and fine to medium GRAVEL, trace silt (SW-GW) (ALLUVIUM or FILL)			2.00										
3			SW-GW			2	HD	15,22,24,36	60	2/2.0					
4		Very Dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND, some GRAVEL (SW-GW) (ALLUVIUM or FILL)			4.00										
5		SW-GW			3	HD	7,23,25,28	53	0/2.0						
6		6.0 FT TOTAL DEPTH OF BOREHOLE			6.00										
7		Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.													
8															

DRILL RIG: CME-55

DRILLING CONTRACTOR: Hawley Brothers

CALLER: Dan Hawley

LOGGED: S Brandenberger

CHECKED: R. Burk

DATE: 3 JANUARY 1990

Golder Associates

PROJECT: WINCO/ICPP/D

## RECORD OF BOREHOLE CPP-55-9

SHEET: 1 OF 1

PROJECT LOCATION: INEL


BORING DATE: 3 JANUARY 1990

DATUM: MSL

PROJECT NUMBER: 893-1195.020

BORING LOCATION: ICPP-55



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE				SAMPLES					PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	20 40 60 80					
					DEPTH						WATER CONTENT, PERCENT					
											Wp	W	W	W		
0	4 INCH HOLLOW STEM AUGER (HSA)	Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, damp, GRAVEL some Sand, (GW) (FILL)	GW		0.00											
1					1	G	N/A		2.0/2.0							
2		Very dense, dark yellowish brown (10YR4/2), unstratified, damp, SAND and fine to medium GRAVEL (SW-GW) (ALLUVIUM or FILL)	SW-GW		2.00											
3					2	HD	20,27,32,33	65	2/2.0							
4		Very dense, brownish gray (5YR4/2), unstratified, damp, SAND and fine to medium GRAVEL (SW-GW) (ALLUVIUM or FILL)	SW-GW	4.00												
5				3	HD	15,27,28,37	65	1.0/2.0								
6		6.0 FT TOTAL DEPTH OF BOREHOLE		6.00												
7		Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.														
8																

DRILLING: CME-55

DRILLING CONTRACTOR: Hawley Brothers

DRILLER: Dan Hawley

Golder Associates

LOGGED: S Brandenberger

CHECKED: R. Gura

DATE: 20 DECEMBER 90

PROJECT: WINCO/ICPP/ID  
 PROJECT LOCATION: INEL  
 PROJECT NUMBER: 893-1195.020

# RECORD OF BOREHOLE CPP-55-10

BORING DATE: 22 DECEMBER 90  
 BORING LOCATION: ICPP-55

SHEET: 1 OF 1

DATUM: MSL



DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT				PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	USCS	GRAPHIC LOG ELEV DEPTH	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	20	40	60	80	
0	4 INCH HOLLOW STEM AUGER (ISA)	Very dense (frozen), dark yellowish brown (10YR4/2), unstratified, SAND and fine GRAVEL some SILT, (FILL)	SW-G		0.00									
1					1	G	N/A		2.0/2.0					
2		Very dense, dark yellowish brown (10YR4/2), unstratified, GRAVEL and fine to medium SAND, trace silt, (SW-GW) (ALLUVIUM or FILL)	SW-G		2.00									
3					2	HD	16,36,30,31	61	7.2/2.0					
4		Dense, grayish brown (5YR3/2) to moderate brown (5YR3/4), unstratified, dry, GRAVEL and medium to coarse SAND, trace silt, (SW-GW) (ALLUVIUM or FILL)	SW-G		4.00									
5					3	HD	17,24,21,24	45	8.2/2.0					
6		6.0 FT TOTAL DEPTH OF BOREHOLE			6.00									
7		Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.												
8														



PROJECT: WINCO/CPP/D

## RECORD OF BOREHOLE CPP-55-11

SHEET: 1 OF 1







PROJECT LOCATION: INEL

BORING DATE: 22 DECEMBER 90

DATUM: MSL

PROJECT NUMBER: 893-1195.020

BORING LOCATION: ICPP-55

DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					PENETRATION RESISTANCE BLOWS/FT ■				PIEZOMETER OR STANDPIPE INSTALLATION						
		DESCRIPTION	USCS	GRAPHIC LOG	ELEV DEPTH	NUMBER	TYPE	BLOWS / 6 in	N	REC/ATT	WATER CONTENT, PERCENT									
											Wp	W <sub>L</sub>	W <sub>p</sub>		W <sub>L</sub>					
0	4 INCH HOLLOW STEM AUGER (ISA)	Very dense (frozen), moderate brown (5YR4/4), unstratified, damp, SAND and GRAVEL, little silt, (SW-GW) (FILL)	SW-GW		0.00	1	G	N/A		2.0/2.0										
1																				
2		Dense, moderate yellowish brown (10YR5/4), unstratified, damp, SAND and fine GRAVEL, some Silt, (SW-GM) (ALLUVIUM or FILL)	SW-GW		2.00	2	HD	8,17,19,12	31	.6/2.0										
3																				
4		Dense, moderate yellowish brown (10YR5/4), unstratified, damp, GRAVEL and medium to coarse SAND, trace silt, (SW-GW) (ALLUVIUM or FILL)	SW-GW		3.00	3	HD	7,11,12,17	29	.6/2.0										
5																				
6	Compact, grayish brown (5YR3/2), unstratified, damp, medium to coarse SAND, little fine Gravel, (SW) (ALLUVIUM or FILL)	SW		4.00																
7																				
8	6.0 FT TOTAL DEPTH OF BOREHOLE			6.00																
		Note: HD refers to a 4.0 inch OD split spoon advanced with a 140 lb. hammer with a 30 inch drop.																		

DRIE: RIG: CME-55

DRILLING CONTRACTOR: Hawley Brothers

DRILLER: Dan Hawley

LOGGED: J. Wozniak

CHECKED: R. Burk

DATE: 22 DECEMBER 90

Golder Associates

**APPENDIX C**  
**QUALITY ASSURANCE SAMPLE ANALYSIS RESULTS**

Table C.1	
Organic Trip Blank Analysis Results	
Land Disposal Unit CPP-55	
Compound	Range of Values, ug/L
Acetone	9 to 49
Methylene Chloride	4

Table C.2			
Equipment Blank Analysis Results			
Land Disposal Unit CPP-55			
Sample ID:	2186-(3,4,5)	2218-(14,15,16)	405-002
Date Sampled:	12/19/89	01/04/90	02/22/90
Iron, ug/L	82.1	<50.0	NA <sup>1</sup>

<sup>1</sup>NA indicates sample was not analyzed for the indicated parameter.

Table C.3			
Field Blank Analysis Results (Deionized Water from Building CPP-609)			
Lab Sample ID:	2202-(16,17,18)	2281-(4,5)	2286-03
Date Sampled:	12/22/89	02/08/90	02/08/90
Iron, ug/L	50.7	<50.0	NA <sup>1</sup>
Trichloroethene, ug/L	<5	<5	2 J <sup>2</sup>

<sup>1</sup>NA indicates the sample was not analyzed for the respective compound/analyte.

<sup>2</sup>J indicates the compound was detected at an estimated concentration indicating the sample result may be less than the contract required detection limit but greater than zero.

Table C.4			
Field Duplicate Analysis Results, (mg/Kg)			
Land Disposal Unit CPP-55			
Laboratory Sample ID:	2191-(1,2,3)	2191-(4,5,6)	%RPD <sup>1</sup>
Golder Sample ID:	CPP55-03-TX-3-1 CPP55-03-V2-3-2 CPP55-03-V3-3-3	CPP55-03-TX-3-4-FD CPP55-03-V2-3-5-FD CPP55-03-V3-3-6-FD	
Borehole Location:	CPP55-03	CPP55-03	
Sample Depth, feet:	2' TO 4'	2' TO 4'	
Date sampled:	12/20/89	12/20/89	
Arsenic	4.9	5.3	7.8
Barium	120	118	1.7
Cadmium	<1.0	<1.0	NC <sup>2</sup>
Chromium	24.4	29.6	19.3
Iron	12,800	13,000	1.6
Lead	7.8	7.4	5.3
Mercury	0.45	0.44	2.2
Nickel	17.0	12.8	28.2
Selenium	<0.54	<0.52	NC <sup>2</sup>
Silver	<2.0	<2.0	NC <sup>2</sup>

<sup>1</sup>Relative percent difference (RPD%) equals the absolute value of the difference between two measurements divided by the average of the two measurements multiplied by 100. For soil matrices a target goal for %RPD is usually 35% for samples that exhibit results at least greater than 5 times the sample detection limit.

<sup>2</sup>NC indicates the RPD cannot be calculated because of one or more result at or below the sample detection limit.

Table C. 4 Continued			
Field Duplicate Analysis Results, (mg/Kg)			
Land Disposal Unit CPP-55			
Laboratory Sample ID:	2218-(28,29,30)	2218-(31,32,33)	%RPD <sup>1</sup>
Golder Sample ID:	CPP55-09-TX-6-9 CPP55-09-V2-6-10 CPP55-09-V3-9-11	CPP55-09-TX-6-12-FD CPP55-09-V2-6-13-FD CPP55-09-V3-6-14-FD	
Borehole Location:	CPP55-09	CPP55-09	
Sample Depth, feet:	4' to 6'	4' to 6'	
Date sampled:	01/03/90	01/03/90	
Arsenic	6.2	6.8	9.0
Barium	108	96.4	11.4
Cadmium	<1.0	<0.99	NC <sup>2</sup>
Chromium	17.9	14.6	20.3
Iron	12,100	10,400	15.1
Lead	7.2	6.4	11.8
Mercury	<0.05	<0.05	NC <sup>2</sup>
Nickel	18.1	14.8	20.1
Selenium	<0.57	<0.60	NC <sup>2</sup>
Silver	<2.0	<2.0	NC <sup>2</sup>

<sup>1</sup>Relative percent difference (RPD%) equals the absolute value of the difference between two measurements divided by the average of the two measurements multiplied by 100. For soil matrices a target goal for %RPD is usually 35% for samples that exhibit results at least greater than 5 times the sample detection limit.

<sup>2</sup>NC indicates the RPD cannot be calculated because of one or more result at or below the sample detection limit.

Table C.5 - Blind Sample Analysis Results Land Disposal Unit CPP-55			
Laboratory Sample ID:	2218-(1,2,3)		
Golder Sample ID:	CPP55-04-V2-2-FB		
Date sampled:	01/04/90		
Compound/Analyte	Reported Value, ug/L	True Value ug/L	Percent Recovery <sup>1</sup>
Methylene Chloride	20	20.8	96
1,1-Dichloroethane	18	20	90
Chloroform	20	20.2	99
1,1,1-Trichloroethane	18	20.2	89
Bromodichloromethane	19	20.2	94
Trichloroethene	18	20.4	88
Dibromochloromethane	19	20.4	93
Benzene	20	20.6	97
Bromoform	17	20	85
1,1,2,2-Tetrachloroethane	17	20	85
Toluene	19	20.6	92
1,2-Dichlorobenzene	17	20	85
Arsenic	4450	5000	89
Selenium	920	1000	92

<sup>1</sup>Percent recovery is calculated by dividing the reported value by the true value and multiplying by 100. For water matrices the target percent recovery is typically 80 to 120 percent.



Table C.6..		
Decontamination Rinseate Analysis Results Land Disposal Unit CPP-55		
Laboratory Sample ID:	2191-(11,12)	2218-(17,18,19)
Golder Sample ID:	CPP55-DCW-TX-11 CPP55-DCW-MH-12	CPP55-02-TX-17-DCW CPP55-02-V2-18-DCW CPP55-02-V3-19-DCW
Date Sampled:	12/20/89	01/04/90
Analyte/Compound	Result, ug/L (except where noted)	
Mineral Spirits <sup>1</sup>	NA <sup>2</sup>	81 mg/L
Methanol	30 mg/L	3.4 mg/L
Arsenic	7.0	16.0
Barium	215	1,800
Cadmium	<5.0	<5.0
Chromium	33.5	96.2
Iron	17,800	52,800
Lead	120	260
Mercury	0.32	<0.10
Nickel	33.6	128
Selenium	<3.0	<3.0
Silver	<10.0	<10.0

<sup>1</sup>High (boiling point) petroleum hydrocarbons quantitated against mineral spirits. This is not a definitive identification. Any hydrocarbon occurring within the approximate boiling range of mineral spirits standard is characterized as, and quantitated as, mineral spirits.

<sup>2</sup>NA signifies analyte/compound was not analyzed for in the respective sample.

**APPENDIX D**  
**BOREHOLE CPP-55-06 ANALYSES**

TABLE D.1

LIST OF ANALYTES/COMPOUNDS ANALYZED  
(APPENDIX VIII COMPOUNDS, CLP ORGANIC COMPOUNDS, CLP  
INORGANIC ANALYTES AND RADIONUCLIDES)

## INORGANIC ANALYTES

Aluminum  
Antimony  
Arsenic  
Barium  
Beryllium  
Cadmium  
Calcium  
Chromium  
Cobalt  
Copper  
Cyanide  
Iron  
Lead  
Magnesium  
Manganese  
Mercury  
Nickel  
Potassium  
Selenium  
Silver  
Sodium  
Sulfide  
Thallium  
Tin  
Vanadium  
Zinc

## VOLATILE ORGANICS

Acetone  
Acetonitrile  
Acrolein  
Acrylonitrile  
Allyl Chloride  
Benzene  
Bromoacetone  
Bromoform  
Carbon Disulfide  
Carbon Tetrachloride  
Chlorobenzene  
1-Chloro-2,3-epoxypropane  
Chlorodibromomethane  
2-Chloroethylvinyl ether  
Chloroethane  
Chloromethyl methyl ether  
Chloroform  
Chloroprene  
Crotonaldehyde  
1,2-Dibromo-3-chloropropane  
1,2-Dibromoethane  
Dibromomethane  
trans-1,4-Dichloro-2-butene  
Dichlorobromomethane  
Dichlorodifluoromethane  
1,1-Dichloroethane  
1,2-Dichloroethane  
1,2-Trans-dichloroethylene  
1,1-Dichloroethylene  
1,3-Dichloropropane  
1,2-Dichloropropane  
2,3-Dichloropropene  
cis-1,3-Dichloropropylene  
trans-1,3-Dichloropropylene  
1,2,3,4-Diepoxybutane  
N,N-Diethylhydrazine  
1,4-Dioxane  
Ethylbenzene  
Ethylcyanide  
Freon TF  
Formaldehyde  
2-Hexanone

## RADIONUCLIDES

Americium 241  
Plutonium 238  
Neptunium  
Antimony 125  
Cobalt 60 & 58  
Iodine 129  
Cerium 144  
Ruthenium 103 & 106  
Cesium 134 & 137  
Strontium 90  
Yttrium 90  
Uranium 234, 235 & 238

Iodomethane  
Isobutyl alcohol  
Methyl bromide  
Methyl chloride  
Methacrylonitrile  
Methyl ethyl ketone  
Methyl hydrazine  
4-Methyl-2-pentanone  
Methylene Chloride  
Paraldehyde  
Pentachloroethane  
Styrene  
1,1,1,2-Tetrachloroethane  
1,1,2,2-Tetrachloroethane  
Tetrachloroethylene  
Tetranitromethane  
Toluene  
1,1,1-Trichloroethane  
1,1,2-Trichloroethane  
Trichloromethanethiol  
Trichloroethylene  
Trichlorofluoromethane  
1,1,2-Trichloropropane  
1,2,2-Trichloropropane  
1,2,3-Trichloropropane  
Vinyl Acetate  
Vinyl Chloride  
Xylene (total)

## SEMI-VOLATILE ORGANICS

Acenaphthene  
Acenaphthylene  
Acetophenone  
2-Acetylaminofluorene  
Aflatoxins, Total  
4-Aminobiphenyl  
5-(Aminomethyl)-3-isoxazolol  
Aniline  
Anthracene  
Aramite  
Auramine  
Benzo(c)acridine  
Benzo(a)anthracene

Table D. 1, Continued

Benzyl Chloride  
 Benzoic Acid  
 Benzyl Alcohol  
 Benzenethiol  
 Benzo(b)fluranthene  
 Benzo(j)fluranthene  
 Benzo(k)fluranthene  
 Benzo(g,h,i)perylene  
 Benzo(a)pyrene  
 Benzotrichloride  
 p-Benzoquinone  
 bis(2-Chloroethyl)ether  
 bis(2-Chloroethoxy)methae  
 bis(2-Chloroisopropyl)ether  
 bis(2-Ethylhexyl)phthalate  
 4-Bromophenyl-phenylether  
 Brucine  
 2-Butanone Peroxide  
 Butyl Benzyl Phthalate  
 2-sec-Butyl-4,6-dinitrophenol  
 Chloronaphazine  
 1-Chloronaphthalene  
 2-Chloronaphthalene  
 2-Chlorophenol  
 4-Chlorophenylphenylether  
 3-Chloropropionitrile  
 Chrysene  
 p-Chloroaniline  
 p-Chloro-m-cresol  
 o-Cresol  
 m-Cresol  
 p-Cresol  
 2-Cyclohexyl-4,6-dinitrophenol  
 Dibenzo(a,h)anthracene  
 Dibenzo(a,h)acridine  
 Dibenzo(a,j)acridine  
 Dibenzo(a,e)pyrene  
 Dibenzo(a,h)pyrene  
 Dibenzofuran  
 Dibenzo(a,i)pyrene  
 7H-Dibenzo(c,g)carbazole  
 1,2-Dichlorobenzene  
 1,3-Dichlorobenzene  
 1,4-Dichlorobenzene  
 3,3-Dichlorobenzidine  
 Dichloromethylbenzene  
 2,4-Dichlorophenol

2,6-Dichlorophenol  
 Dichlorophenylarsine  
 Diethylphthalate  
 Dihydrosafrole  
 Diisopropylfluorophosphate  
 p-Dimethylaminoazobenzene  
 3,3'-Dimethylbenzidine  
 7,12-Dimethylbenzo(a)anthcene  
 1,1-Dimethylhydrazine  
 1,2-Dimethylhydrazine  
 a-a-Dimethylphenethylamine  
 Dimethyl Phthalate  
 2,4-Dimethylphenol  
 Di-n-butyl Phthalate  
 2,4-Dinitrophenol  
 Dimethyl Sulfate  
 m-Dinitrobenzene  
 4,6-Dinitro-o-cresol  
 2,4-Dinitrotoluene  
 2,6-Dinitrotoluene  
 Di-n-octyl Phthalate  
 Diphenylamine  
 1,2-Diphenylhydrazine  
 2,4-Dithiobiuret  
 Endothal  
 Ethyl Methacrylate  
 Ethyl Methanesulfonate  
 Fluoranthene  
 Fluorene  
 Formic Acid  
 Hexachlorobenzene  
 Hexachlorobutadiene  
 Hexachlorocyclopentadiene  
 Hexachloroethane  
 Hexachlorophene  
 Hexachloropropene  
 Hexaethyltetraphosphate  
 Hydrazine  
 Indeno(1,2,3-cd)pyrene  
 Isophorone  
 Isosafrole  
 Maleic Anhydride  
 Melphalan  
 Methapyrilene  
 3-Methylcholanthrene  
 Methyl Methacrylate  
 4,4-Methylenebis(2-chloroanilin)

2-Methylactonitrile  
 Methyl Methanesulfonate  
 N-Methyl-N-nitroso-N-nitroqua  
 2-Methylnaphthalene  
 Methylthiouracil  
 Naphthalene  
 1,4-Naphthoquinoline  
 1-Naphthylamine  
 2-Naphthylamine  
 p-Nitroaniline  
 m-Nitroaniline  
 o-Nitroaniline  
 Nitrobenzene  
 2-Nitrophenol  
 4-Nitrophenol  
 N-Nitrosodi-n-butylamine  
 N-Nitrosodiethanolamine  
 N-Nitrosodimethylamine  
 N-Nitrosomethylethylamine  
 N-Nitroso-n-methylurethane  
 N-Nitrosomethylvinylamine  
 N-Nitrosomorpholine  
 N-Nitrososornicotine  
 N-Nitrosodi-n-propylamine  
 N-Nitroquinoline-n-oxide  
 N-Nitrosospiperidine  
 N-Nitrosopyrrolidine  
 N-Nitrosodiphenylamine  
 N-Nitrososarcosine  
 5-Nitro-o-toluidine  
 Octamethylpyrophosphoramide  
 Paraoxon  
 Pentachlorobenzene  
 Pentachloroethane  
 Pentachloronitrobenzene  
 Pentachlorophenol  
 Phenanthrene  
 Phenacetin  
 Phenol  
 p-Phenylenediamine  
 Phthalic Anhydride  
 2-Picoline  
 Pronamide  
 1,3-Propane Sultone  
 n-Propylamine  
 Propylthiouracil

Table D. 1 Continued

Pyrene  
 Pyridine  
 Resorcinol  
 Saccharin  
 Safrole  
 1,2,3,4-Tetrachlorobenzene  
 1,2,3,5-Tetrachlorobenzene  
 1,2,4,5-Tetrachlorobenzene  
 2,3,4,6-Tetrachlorophenol  
 o-Toluidine  
 Thiuram  
 sym-Trinitrobenzene  
 tris(1-Azridinyl)phosphine sul  
 tris(2,3-Dibromopropyl)phospha  
 2,3,5,6-Tetrachlorophenol  
 2,3,4,5-Tetrachlorophenol  
 Thiofanox  
 1,2,3-Trichlorobenzene  
 1,2,4-Trichlorobenzene  
 1,3,5-Trichlorobenzene  
 2,4,5-Trichlorophenol  
 2,4,6-Trichlorophenol  
 Uracil Mustard

**ORGANOCHLORINE  
 PESTICIDES AND PCBs**

Aldrin  
 Alpha-BHC  
 Beta-BHC  
 Delta-BHC  
 Gamma-BHC  
 Chlorobenzilate  
 Chlordane  
 4,4'-DDD  
 4,4'-DDE  
 4,4'-DDT  
 Diallyate  
 Dieldrin  
 Endosulfan I  
 Endosulfan II  
 Endosulfan Sulfate  
 Endrin  
 Endrin Aldehyde  
 Endrin Ketone  
 Heptachlor  
 Heptachlor Epoxide

Isodrin  
 Kepone  
 Methoxychlor  
 Toxaphene  
 Aroclor-1016  
 Aroclor-1221  
 Aroclor-1232  
 Aroclor-1242  
 Aroclor-1248  
 Aroclor-1254  
 Aroclor-1260

**HERBICIDES**

2,4-D  
 2,4,5-TP  
 2,4,5-T

**ORGANOPHOSPHORUS  
 PESTICIDES**

Dimethoate  
 Disulfoton  
 Famphur  
 Methyl Parathion  
 Parathion  
 Phorate  
 Sulfotepp  
 Thionazin  
 o,o,o-Triethylphosphorothioate

**ALCOHOLS**

Acetonitrile; methyl cyanide  
 1,4-Dioxane  
 Isobutyl alcohol

**DIOXINS**

Tetrachlorodibenzodioxin (TCDD)  
 Pentachlorodibenzodioxin  
 (PeCDD)  
 Hexachlorodibenzodioxin  
 (HxCDD)  
 Heptachlorodibenzodioxin  
 (HpCDD)  
 Octachlorodibenzodioxin (OCDD)

Tetrachlorodibenzofuran  
 (TCDF)  
 Pentachlorodibenzofuran  
 (PeCDF)  
 Hexachlorodibenzofuran  
 (HxCDF)  
 Heptachlorodibenzofuran  
 (HeCDF)  
 Octachlorodibenzofuran  
 (OCDF)

TABLE D.2

## LIST OF ANALYTES/COMPOUNDS ANALYZED FOR BUT NOT DETECTED

## INORGANIC ANALYTES

Antimony  
Cyanide  
Thallium  
Tin

## RADIONUCLIDES

Americium 241  
Antimony 125  
Cobalt 60 & 58  
Cerium 144  
Ruthenium 103 & 106  
Cesium 134  
Uranium 235  
Iodine 129

## VOLATILE ORGANICS

Acetonitrile  
Acrolein  
Acrylonitrile  
Allyl Chloride  
Benzene  
Bromoacetone  
Bromoform  
Carbon Disulfide  
Carbon Tetrachloride  
Chlorobenzene  
1-Chloro-2,3-epoxypropane  
Chlorodibromomethane  
2-Chloroethylvinyl ether  
Chloroethane  
Chloromethyl methyl ether  
Chloroprene \*  
Crotonaldehyde  
1,2-Dibromo-3-chloropropane  
1,2-Dibromoethane  
Dibromomethane  
trans-1,4-Dichloro-2-butene  
Dichlorobromomethane  
Dichlorodifluoromethane \*  
1,1-Dichloroethane  
1,2-Dichloroethane  
1,2-Trans-dichloroethylene

1,1-Dichloroethylene  
1,3-Dichloropropane  
1,2-Dichloropropane  
2,3-Dichloropropene  
cis-1,3-Dichloropropylene  
trans-1,3-Dichloropropylene  
1,2,3,4-Diepoxybutane  
N,N-Diethylhydrazine  
1,4-Dioxane  
Ethylbenzene  
Ethylcyanide \*  
Freon TF  
Formaldehyde  
2-Hexanone  
Iodomethane  
Isobutyl alcohol  
Methyl bromide  
Methyl chloride  
Methacrylonitrile  
Methyl hydrazine  
Paraldehyde  
Pentachloroethane  
Styrene  
1,1,1,2-Tetrachloroethane  
1,1,2,2-Tetrachloroethane  
Tetrachloroethylene  
Tetranitromethane  
1,1,1-Trichloroethane  
1,1,2-Trichloroethane  
Trichloromethanethiol  
Trichloroethylene  
Trichlorofluoromethane  
1,1,2-Trichloropropane  
1,2,2-Trichloropropane  
1,2,3-Trichloropropane  
Vinyl Acetate  
Vinyl Chloride  
Xylene (total)

## SEMI-VOLATILE ORGANICS

Acenaphthene  
Acenaphthylene  
Acetophenone  
2-Acetylaminofluorene  
Aflatoxins, Total

4-Aminobiphenyl  
5-(Aminomethyl)-3-isoxazolol  
Aniline \*  
Anthracene  
Aramite \*  
Auramine \*\*  
Benzo(c)acridine  
Benzo(a)anthracene  
Benzyl Chloride  
Benzoic Acid  
Benzyl Alcohol  
Benzenethiol  
Benzo(b)fluoranthene  
Benzo(j)fluoranthene  
Benzo(k)fluoranthene  
Benzo(g,h,i)perylene  
Benzo(a)pyrene  
Benzotrichloride  
p-Benzoquinone  
bis(2-Chloroethyl)ether  
bis(2-Chloroethoxy)methae  
bis(2-Chloroisopropyl)ether  
4-Bromophenyl-phenylether  
Brucine  
2-Butanone Peroxide \*\*  
Butyl Benzyl Phthalate  
2-sec-Butyl-4,6-dinitrophenol  
Chloronaphazine \*\*  
1-Chloronaphthalene  
2-Chloronaphthalene  
2-Chlorophenol  
4-Chlorophenylphenylether  
3-Chloropropionitrile  
Chrysene  
p-Chloroaniline  
p-Chloro-m-cresol  
o-Cresol  
m-Cresol  
p-Cresol  
2-Cyclohexyl-4,6-dinitrophenol  
Dibenzo(a,h)anthracene  
Dibenzo(a,h)acridine  
Dibenzo(a,j)acridine  
Dibenzo(a,e)pyrene  
Dibenzo(a,h)pyrene  
Dibenzofuran

Table D. 2. Continued

Dibenzo(a,i)pyrene  
 7H-Dibenzo(c,g)carbazole  
 1,2-Dichlorobenzene  
 1,3-Dichlorobenzene  
 1,4-Dichlorobenzene  
 3,3-Dichlorobenzidine \*  
 Dichloromethylbenzene  
 2,4-Dichlorophenol  
 2,6-Dichlorophenol  
 Dichlorophenylarsine \*\*  
 Diethylphthalate  
 Dihydrosafrole \*\*  
 Diisopropylfluorophosphate \*\*  
 p-Dimethylaminoazobenzene  
 3,3'-Dimethylbenzidine  
 7,12-Dimethylbenzo(a)anthracene  
 1,1-Dimethylhydrazine  
 1,2-Dimethylhydrazine  
 a-a-Dimethylphenethylamine  
 Dimethyl Phthalate  
 2,4-Dimethylphenol  
 Di-n-butyl Phthalate  
 2,4-Dinitrophenol  
 Dimethyl Sulfate  
 m-Dinitrobenzene  
 4,6-Dinitro-o-cresol  
 2,4-Dinitrotoluene  
 2,6-Dinitrotoluene  
 Di-n-octyl Phthalate  
 Diphenylamine  
 1,2-Diphenylhydrazine  
 2,4-Dithiobiuret \*\*  
 Endothal \*\*  
 Ethyl Methacrylate  
 Ethyl Methanesulfonate  
 Fluoranthene  
 Fluorene  
 Formic Acid  
 Hexachlorobenzene \*  
 Hexachlorobutadiene  
 Hexachlorocyclopentadiene  
 Hexachloroethane  
 Hexachlorophene \*  
 Hexachloropropene \*  
 Hexaethyltetraphosphate \*\*  
 Hydrazine  
 Indeno(1,2,3-cd)pyrene

Isophorone  
 Isosafrole  
 Maleic Anhydride  
 Melphalan \*\*  
 Methapyrilene  
 3-Methylcholanthrene  
 Methyl Methacrylate  
 4,4-Methylenebis(2-chloroanil  
 2-Methylactonitrile  
 Methyl Methanesulfonate  
 N-Methyl-N-nitroso-N-nitrogu  
 2-Methylnaphthalene  
 Methylthiouracil  
 Naphthalene  
 1,4-Naphthoquinoline  
 1-Naphthylamine  
 2-Naphthylamine  
 p-Nitroaniline  
 m-Nitroaniline  
 o-Nitroaniline  
 Nitrobenzene  
 2-Nitrophenol  
 4-Nitrophenol  
 N-Nitrosodi-n-butylamine  
 N-Nitrosodiethanolamine \*\*  
 N-Nitrosodiethylamine  
 N-Nitrosodimethylamine  
 N-Nitrosomethylethylamine  
 N-Nitroso-n-methylurethane  
 N-Nitrosomethylvinylamine  
 N-Nitrosomorpholine  
 N-Nitrososornicotine \*\*  
 N-Nitrosodi-n-propylamine  
 N-Nitroquinoline-n-oxide  
 N-Nitrosospiperidine  
 N-Nitrosopyrrolidine  
 N-Nitrosodiphenylamine  
 N-Nitrososarcosine  
 5-Nitro-o-toluidine  
 Octamethylpyrophosphoramid  
 Paraoxon  
 Pentachlorobenzene  
 Pentachloroethane  
 Pentachloronitrobenzene  
 Pentachlorophenol  
 Phenanthrene  
 Phenacetin

Phenol  
 p-Phenylenediamine  
 Phthalic Anhydride  
 2-Picoline \*  
 Pronamide  
 1,3-Propane Sultone \*\*  
 n-Propylamine  
 Propylthiouracil  
 Pyrene  
 Pyridine \*  
 Resorcinol  
 Saccharin  
 Safrole  
 1,2,3,4-Tetrachlorobenzene  
 1,2,3,5-Tetrachlorobenzene  
 1,2,4,5-Tetrachlorobenzene  
 2,3,4,6-Tetrachlorophenol  
 o-Toluidine  
 Thiuram  
 sym-Trinitrobenzene  
 tris(1-Azridinyl)phosphine sul  
 \*\*  
 tris(2,3-Dibromopropyl)phospha  
 2,3,5,6-Tetrachlorophenol  
 2,3,4,5-Tetrachlorophenol  
 Thiofanox  
 1,2,3-Trichlorobenzene  
 1,2,4-Trichlorobenzene  
 1,3,5-Trichlorobenzene  
 2,4,5-Trichlorophenol  
 2,4,6-Trichlorophenol  
 Uracil Mustard \*\*

**ORGANOCHLORINE  
 PESTICIDES AND PCBs**

Aldrin  
 Alpha-BHC  
 Beta-BHC  
 Delta-BHC  
 Gamma-BHC  
 Chlorobenzilate  
 Chlordane  
 4,4'-DDD  
 4,4'-DDE  
 4,4'-DDT  
 Diallate

Table D.2 Continued

Dieldrin  
 Endosulfan I  
 Endosulfan II  
 Endosulfan Sulfate  
 Endrin  
 Endrin Aldehyde  
 Endrin Ketone  
 Heptachlor  
 Heptachlor Epoxide  
 Isodrin  
 Kepone \*  
 Methoxychlor  
 Toxaphene  
 Aroclor-1016  
 Aroclor-1221  
 Aroclor-1232  
 Aroclor-1242  
 Aroclor-1248  
 Aroclor-1254  
 Aroclor-1260

**HERBICIDES**

2,4-D  
 2,4,5-TP  
 2,4,5-T

**ORGANOPHOSPHORUS  
PESTICIDES**

Dimethoate  
 Disulfoton  
 Famphur  
 Methyl Parathion  
 Parathion  
 Phorate  
 Sulfotepp  
 Thionazin  
 o,o,o-Triethylphosphorothioate

**ALCOHOLS**

Acetonitrile; methyl cyanide  
 1,4-Dioxane  
 Isobutyl alcohol

**DIOXINS**

Tetrachlorodibenzodioxin  
 (TCDD)  
 Pentachlorodibenzodioxin  
 (PeCDD)  
 Hexachlorodibenzodioxin  
 (HxCDD)  
 Heptachlorodibenzodioxin  
 (HpCDD)  
 Octachlorodibenzodioxin  
 (OCDD)  
 Tetrachlorodibenzofuran  
 (TCDF)  
 Pentachlorodibenzofuran  
 (PeCDF)  
 Hexachlorodibenzofuran  
 (HxCDF)  
 Heptachlorodibenzofuran  
 (HpCDF)  
 Octachlorodibenzofuran  
 (OCDF)

\* Compounds were analyzed by performing an NBS spectral library search. Reference standards were not available.

\*\* Compound could not be analyzed for as no reference standard was available nor reference spectra present in the NBS spectral library.